

# I-81 VIADUCT PROJECT - PHASE 1, CONTRACT 1

PIN 3501.90, Contract D900054

# DB CONTRACT DOCUMENTS REQUEST FOR PROPOSALS

PART 7
ENGINEERING DATA
(PART 5 OF 5)


**Draft May 17, 2022** 

# **ENGINEERING DATA**

**TABLE OF CONTENTS** 


STRUCTURAL DETAILS **RESTORATION PLANS** HAZARDOUS WASTE CONTAMINATED MATERIALS ADDITIONAL INFORMATION

# **Structural Details**



 PROVIDE DIMENSION TO AVOID INTERFERENCE WITH THE REINFORCEMENT.

# KEYWAY DETAIL




LONGITUDINAL UHPC JOINT


	UHPC JOINT TABLE						
BAR SIZE	JOINT	JOINT PROTRUSION SPLICE	SPLICE	CLEAR	SPACING		
DAR SIZE	WIDTH	LENGTH	LENGTH	MINIMUM	MAXIMUM		
#4	6"	5"	4"	1"	4"		
<b>*</b> 5	7"	6"	5"	11/4"	5"		
#6	9"	71/2"	6"	11/2"	6"		

DESIGNER NOTE:

UHPC JOINT TABLE IS APPLICABLE FOR ALL BAR TYPES WITH A YIELD STRENGTH NO GREATER THAN 75 KSI.







# SEMI-INTEGRAL ABUTMENT CONSTRUCTION PROCEDURE

- 1. PLACE FOOTING, ABUTMENT STEM, AND PEDESTALS.
- 2. BACKFILL ABUTMENT STEMS TO 6" BELOW THE BRIDGE SEAT ELEVATION. NO BACKFILL OF THE ABUTMENT STEMS ALLOWED UNTIL THE ABUTMENTS HAVE CURED FOR
- 3. PLACE STONE FILL OR SLOPE PROTECTION.
- 4. ERECT GIRDERS AND INSTALL ALL DIAPHRAGMS.
- 5. PLACE ABUTMENT BACKWALL AND DECK CONCRETE.
- 6. BACKFILL ABUTMENT BACKWALLS. NO BACKFILLING OF THE ABUTMENT IS ALLOWED UNTIL BACKWALLS HAVE CURED FOR 7 DAYS. BACKFILLING SHALL BE CONDUCTED SUCH THAT THE MAXIMUM DIFFERENTIAL IN FILL HEIGHT BETWEEN THE TWO ABUTMENTS (AS MEASURED FROM THE BOTTOM OF THE BACKWALL) DOES NOT EXCEED 2 ft. IN ADDITION, THE FILL HEIGHT BEHIND ANY SINGLE ABUTMENT BACKWALL SHALL NOT VARY MORE THAN 2 ft.
- 7. PLACE CONCRETE FOR APPROACH SLABS.

#### DESIGNER NOTES:

ISOTROPIC DECK REINFORCEMENT FOR SKEWS 30° AND UNDER SHOWN. FOR TRADITIONAL DECK REINFORCEMENT, SEE BD-SS10 & 11.

EPOXY-COATED (E) BARS SHOWN. REFER TO BRIDGE MANUAL, SECTION 15.12 FOR THE REQUIREMENTS OF CORROSION PROTECTED REINFORCEMENT IN

EVERY BAY SHALL HAVE AN INTERMEDIATE TYPE DIAPHRAGM INSTALLED AT THE CENTERLINE OF BEARINGS OF EACH ABUTMENT. FOR TYPICAL DIAPHRAGM DETAILS, SEE THE BD-SG DRAWINGS.

WEEPHOLES SHALL BE PROVIDED IN THE ABUTMENT STEM AT A MAXIMUM SPACING OF 25'-0".

FOR JOINT RECESS DETAIL, SEE BD-ID6.

END DIAPHRAGM NOT SHOWN FOR CLARITY.


\* SPACING SHOWN FOR THESE BARS ARE PARALLEL OR PERPENDICULAR TO STATION LINE OR GIRDER.


TYPICAL 6" COMPOSITE STUD SHEAR CONNECTORS ON TOP OF GIRDER NOT SHOWN FOR CLARITY.

REINFORCEMENT IN BACKWALL SHALL HAVE 2" COVER.


(E) DENOTES EPOXY-COATED BARS.

REVISED	NEW YORK STATE OF OPPORTUNITY.	epartment of Transportation Office of Structures		
	ALTERNATE SEMI-INTEGRAL			
ERRATA	ABUIM	ENT DETAILS		
	APPROVED: / / ORIGINAL SIGNED BY	ORIGINAL ISSUED UNDER EB CURRENT ISSUED UNDER EB		
	DEPUTY CHIEF ENGINEER (STRUCTURES)	EFFECTIVE WITH THE LETTING OF //		







ELEVATION




ISOMETRIC OF BARRIER TRANSITION

NEW YORK STATE OF OPPORTUNITY.	D	epartment of Transportation Office of Structures
BARRIER TO	PIE	R TRANSITION DETAILS
/ / IGNED BY:		ORIGINAL ISSUED UNDER EB
TEE ENGINEED (CTDUCT	CURRENT ISSUED UNDER EB EFFECTIVE WITH THE LETTING OF //	
	BARRIER TO  IGNED BY:	BARRIER TO PIE






UHPC LINK SLAB DETAIL
PRECAST DECK PANELS
(DECK REPLACEMENT SHOWN, NEW SUPERSTRUCTURE SIMILAR)



SCHEMATIC UHPC LINK SLAB DETAIL
JOINT REPLACEMENT - CONCRETE OVERLAY



SCHEMATIC UHPC LINK SLAB DETAIL JOINT REPLACEMENT - WITHOUT GIRDER HAUNCH

#### DESIGNER NOTES:

THE EPOXY COATED BARS SHOWN MAY NEED TO BE CHANGED TO MEET THE REINFORCEMENT CORROSION PROTECTION REQUIREMENTS SPECIFIED IN THE BRIDGE MANUAL.

THE MINIMUM GIRDER END GAP SHALL BE INDICATED IN THE NOTES.
THIS GAP SHALL BE MAXIMIZED TO THE LARGEST EXTENT FEASIBLE
WHILE CONSIDERING THE EXISTING GAP, ALLOWANCES FOR MINOR
AMOUNTS OF SUPERSTRUCTURE MOVEMENT/SHIFTING DURING
CONSTRUCTION OPERATIONS, AND PREVENTING THE GIRDER'S BOTTOM
FLANGES FROM CONTACTING EACH OTHER WHEN ADJOINING SPANS ARE
SIMULTANEOUSLY SUBJECT TO LIVE LOADS.

THE PRECAST DECK PANELS DETAIL DEPICTS TRADITIONAL REINFORCEMENT AND A STANDARD UHPC HAUNCH. THIS DETAIL SHALL BE MODIFIED WHEN USING ISOTROPIC REINFORCEMENT AND/OR A LOW PROFILE HAUNCH.

WHEN USING AN ASPHALT OVERLAY, IT SHALL BE PLACED OVER THE UHPC LINK SLAB. PLACING THE UHPC 0.25 INCHES ABOVE THE CONCRETE DECK SURFACE AND GRINDING FLUSH IS STILL REQUIRED.

SCHEMATIC DETAILS ARE ONLY INTENDED TO SHOW ACCEPTABLE MODIFICATIONS TO THE LINK SLAB, AND DECK END, GEOMETRY FOR VARIOUS EXISTING CONDITIONS. ALL OF THE REQUIREMENTS AND ANNOTATIONS PROVIDED IN THE UHPC LINK SLAB JOINT REPLACEMENT DETAILS SHALL APPLY AND BE SHOWN ON THE CONTRACT PLANS.

#### NOTES:

- 1. WHERE EXISTING BARS ARE DAMAGED DURING REMOVAL OF EXISTING DECK CONCRETE, DRILL AND GROUT \*5(E) DOWELS CENTERED BETWEEN EXISTING DECK BARS TO MATCH SPACING AT NO COST TO THE STATE. GROUT MATERIAL CONFORMING TO NYS MATERIAL SPECIFICATION 701-05 INSTALLED IN ACCORDANCE WITH THE NYS STANDARD SPECIFICATION SECTION 586-3.01. NON-DESTRUCTIVE INVESTIGATION AND PULL DILL TEST NOT REGULIEFD.
- 2. EXISTING STUD SHEAR CONNECTORS MAY REMAIN UNLESS THEY INTERFERE WITH THE DEBONDED ZONE OF THE UHPC LINK SLAB.
- 3. STUD SHEAR CONNECTOR SPACING UNDERNEATH THE LINK SLAB SHALL NOT EXCEED 5 INCHES IN ANY DIRECTION. THE USE OF OTHER TYPES OF SHEAR CONNECTORS ARE PROHIBITED.
- 4. LONGITUDINAL REINFORCEMENT SPLICES ARE NOT PERMITTED IN THE DEBONDED ZONE.
- 5. COMPRESSED SYNTHETIC SHEET GASKET (0.0625 INCH THICK SHEET, TREATED BOTH SIDES), CONFORMING TO MATERIAL SPECIFICATION 728-06, SHALL COVER THE ENTIRE SURFACE OF RECONSTRUCTED DECK ENDS, OR PRECAST PANEL ENDS, WITHIN THE DEBONDED ZONE. COST TO BE INCLUDED IN THE UNIT PRICE BID FOR THE CONCRETE ITEM.
- 6. A MINIMUM GIRDER END GAP OF \_\_\_ INCHES SHALL BE PROVIDED BETWEEN ADJACENT SPANS. THIS MUST BE VERIFIED PRIOR TO POURING THE LINK SLAB. ANY ADJUSTMENTS REQUIRED SHALL BE MADE AT NO ADDITIONAL COST TO THE STATE.
- 7. UPON INSTALLATION OF THE PROPOSED BEARINGS, THE CONTRACTOR SHALL INSTALL TEMPORARY BLOCKING TO ENSURE GLOBAL STABILITY OF THE ENTIRE SUPERSTRUCTURE SYSTEM PRIOR TO THE INSTALLATION OF THE LINK SLABIS, THE CONTRACTOR SHALL SUBMIT THE TEMPORARY BLOCKING PROCEDURE TO THE DCES FOR APPROVAL PRIOR TO THE REMOVAL OF THE EXISTING BEARINGS. THE COST OF TEMPORARY BLOCKING SHALL BE INCLUDED IN THE BEARING REMOVAL ITEMS. AS PART OF THE SUBMITTAL, THE CONTRACTOR MUST SUBMIT A SCHEDULE FOR CHECKING THAT THE BLOCKING MECHANISMS INSTALLED ARE FUNCTIONING AS INTENDED, AND FOR PERFORMING ROUTINE MAINTENANCE, SUCH AS MAKING ADJUSTMENTS FOR THE SUPERSTRUCTURE'S THERMAL MOVEMENTS, FOR THE DURATION OF THE TIME THAT THEY REMAIN IN PLACE.
- 8. IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 565-3.05
  AND AFTER ALL LINK SLABS HAVE CURED FOR A MINIMUM OF SEVEN
  DAYS, THE ALIGNMENT OF ALL EXPANSION BEARINGS SHALL BE
  MEASURED AND ADJUSTMENTS MADE IF REQUIRED.
- 9. (E) DENOTES EPOXY COATED BARS.

REVISED	NEW YORK STATE OF OPPORTUNITY.	Department of Transportation Office of Structures
ERRATA	_ · · · ·	C LINK SLAB ILS (1 OF 2)
	APPROVED: / / ORIGINAL SIGNED BY	ORIGINAL ISSUED UNDER EB
	DEPUTY CHIEF ENGINEER (STRUCTURES)	CURRENT ISSUED UNDER EB EFFECTIVE WITH THE LETTING OF / /

EXISTING CONCRETE BARRIER

CONSTRUCTION JOINT (TYP.)

EXISTING BAR TO REMAIN (TYP.) -


RECONSTRUCTED DECK END (TYP.)

ELEVATION RELIEF JOINT OVER UHPC LINK SLAB
(SINGLE SLOPE CONCRETE BARRIER SHOWN, SIDEWALK AND BRUSH CURB SIMILAR)


(VERTICAL FACED CONCRETE PARAPET WITH SIDEWALK)

SIDEWALK


STEEL GIRDER (TYP.)



SECTION A-A (SINGLE SLOPE CONCRETE BRIDGE BARRIER)



SECTION A-A (SINGLE SLOPE CONCRETE MEDIAN BARRIER)



SEE SECTION A-A AND NOTE 3

- EXISTING DECK

ULTRA-HIGH PERFORMANCE

SHEET GASKET, SEE NOTE 1

CONCRETE LINK SLAB

#### DESIGNER NOTE:

THE DETAILS ON THIS DRAWING DEPICT A UHPC LINK SLAB INSTALLED IN AN EXISTING CAST-IN-PLACE DECK. SIMILAR DETAILS SHALL BE USED FOR PRECAST DECK PANELS.


# NOTES:

- 1. COMPRESSED SYNTHETIC SHEET GASKET (0.0625 INCH THICK SHEET, TREATED BOTH SIDES), CONFORMING TO MATERIAL SPECIFICATION 728-06, SHALL COVER THE ENTIRE SURFACE OF RECONSTRUCTED DECK ENDS, OR PRECAST PANEL ENDS, WITHIN THE DEBONDED ZONE. COST TO BE INCLUDED IN THE UNIT PRICE BID FOR THE CONCRETE ITEM.
- 2. DEBOND ALL REINFORCEMENT THAT EXTENDS OUT OF THE UHPC LINK SLAB WITHIN THE DEBONDED ZONE AS INDICATED IN THE DETAILS. DEBONDING SHALL BE ACCOMPLISHED BY WRAPPING BARS WITH A MINIMUM OF 3 LAYERS OF HEAVY DUTY DUCT TAPE.
- 3. BOND BREAKER USED AT THE INTERFACE OF THE LINK SLAB AND BARRIER, SIDEWALK, OR BRUSH CURB SHALL BE SIKA BONDBREAKER W, WAX BASED BOND BREAKER MATERIAL, OR APPROVED EQUAL.
- 4. THE COST OF THE HYDROPHILIC CAULK/SEAL SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE LINK SLAB CONCRETE ITEM. THE CAULK/SEAL MANUFACTURER AND INSTALLATION SHALL BE APPROVED BY THE ENGINEER. THE HYDROPHILIC CAULK/SEAL SHALL BE PROTECTED
- 5. THE BARS SHOWN IN THE BARRIER ARE THE ANCHORAGE BARS ORIGINATING IN THE DECK. FOR BARRIER REINFORCEMENT DETAILS SEE THE BD-RCB SERIES.

REVISED	NEW YORK STATE OF OPPORTUNITY.	epartment of Transportation Office of Structures
ERRATA		LINK SLAB ILS (2 OF 2)
	APPROVED: / / ORIGINAL SIGNED BY  DEPUTY CHIEF ENGINEER (STRUCTURES)	ORIGINAL ISSUED UNDER EB CURRENT ISSUED UNDER EB EFFECTIVE WITH THE LETTING OF / /



FILE NAME DATE/TIME





# **UHPC Link Slab Design**


	BIN:	
	PIN:	
Job Title:		

# **EXAMPLE**

The NYSDOT Office of Structures has developed an innovative link slab design utilizing Ultra-High Performance Concrete (UHPC). The results of our investigation into the behavior of UHPC link slabs showed that the force required to strain the UHPC in pure tension is extremely large and nearly all of the translation, due to the girder's end rotation, will occur at the bearings. Therefore, the link slab design assumes that the UHPC section is subject to bending only. Although not accounted for in the design of the link slab, due to the conservative approach taken for bending, the link slab also acts as a semi-rigid link that transfers lateral loads between spans.

Our design uses a strain based analysis, where the extreme fiber tensile strain in the UHPC is determined by the amount of girder end rotation, under the assumption of linearly elastic flexural behavior. Using stress-strain relationships, the location of the neutral axis is found through an iterative algorithm. Upon convergence of the assumed and calculated neutral axis location, the tensile strain and compressive stress in the UHPC, along with the stress in the longitudinal steel reinforcement, is computed and compared to allowable values.

In tension, UHPC develops closely spaced micro-cracks as a result of its high strength steel fibers being dispersed throughout a matrix of fine aggregates and supplementary cementitious materials. Due to this unique tensile behavior, UHPC has the ability to withstand ultimate tensile strains up to 0.007. It is this attribute that allows UHPC link slabs to accommodate the girder's end rotations within a relatively short length. For design, a maximum strain of 0.0035 at the extreme tensile fiber was chosen in order to limit the crack widths to a level that will not permit the penetration of moisture and chlorides, ensuring a highly durable solution for the elimination of deck joints.





# **UHPC Link Slab Design**

# **EXAMPLE**

# **User Inputs**

- Indicates user input

 $f_v := 60 \text{ksi}$ 

reinforcement yield strength

 $E_s := 29000 ksi$ 

reinforcement modulus of elasticity (LRFD 5.4.3.2)

$$A_{S} := \frac{0.31 \text{in}^2}{8 \text{in}} = 0.47 \cdot \frac{\text{in}^2}{\text{ft}}$$

area of longitudinal reinforcement at joint

 $\theta_{LL} := 0.00506$ rad

unfactored live load girder end rotation (use average rotation of linked spans if they are not equal)

 $L_{dz} := 16in$ 

debonded zone length

 $d_{bf} := 6.32ft$ 

vertical distance from top of deck to bottom of bottom flange

Note: The following inputs are standard and not editable by the user.

 $E_c := 8000 ksi$ 

**UHPC** compressive modulus of elasticity

 $f_{uhpc.t.all} := 1.2ksi$ 

UHPC tensile cracking stress

 $f_{uhpc.c.all} := -14ksi$ 

maximum allowable UHPC compressive stress

$$\varepsilon_{\text{uhpc.t.all}} := 3500 \ 10^{-6}$$

maximum allowable UHPC tensile strain

 $d_{uhpc} := 4in$ 

depth of UHPC

# Flexural Analysis of Link Slab

width of section b := 1 ft

 $A_s := A_s \cdot b = 0.47 \cdot in^2$ 

area of reinforcement within section

 $c := \begin{bmatrix} eci \leftarrow 1 & 10^{-6} \\ ec \leftarrow 1 \\ i \leftarrow 1 \end{bmatrix}$ 

iterative algorithm to determine distance from bottom of section to neutral axis

while eci < ec

 $h := \, d_{uhpc} = 4.0 \cdot in \qquad \text{ depth of UHPC}$ 

 $f_t := f_{uhpc.t.all} = 1.2 \cdot ksi$ 

assumed maximum tensile stress of UHPC

 $\theta := 1.75 \cdot \theta_{LL} = 0.51 \cdot \deg$ 

Strength I girder end rotation

$$fc \leftarrow eci \cdot E_c$$

$$c \leftarrow \frac{\sqrt{A_s^2 \cdot E_s^2 \cdot eci}^2 + fc \cdot A_s \cdot E_s \cdot b \cdot h \cdot eci + b^2 \cdot f_t^2 \cdot h^2} + b \cdot f_t \cdot h - A_s \cdot E_s \cdot eci}{b \cdot f_c + 2 \cdot b \cdot f_t}$$

$$ec \leftarrow \frac{-2 \cdot \theta \cdot c}{L_{dz}}$$

$$eci \leftarrow eci + 0.1 \cdot 10^{-6}$$

$$i \leftarrow i + 1$$

out 
$$\leftarrow$$
 "Error" if  $(c < 0 \text{in}) \lor (c > d_{uhpc}) \lor \left(\frac{\text{max}(|ec|, eci)}{\text{min}(|ec|, eci)} - 1 > 5\%\right)$ 


out  $\leftarrow$  c otherwise

return out


# UHPC Link Slab Design

# **EXAMPLE**

# Strain Diagram



# Stress Diagram



distance from bottom of section to neutral axis  $c = 1.04 \cdot in$ 

$$\varepsilon_{uhpc.t} \coloneqq \frac{2 \cdot \theta \cdot \left(d_{uhpc} - c\right)}{L_{dz}} = 3280 \cdot 10^{-6} \qquad \text{tensile strain in UHPC}$$

$$\varepsilon_{s.t} \coloneqq \frac{2 \cdot \theta \cdot \left(\frac{d_{uhpc}}{2} - c\right)}{L_{dz}} = 1067 \cdot 10^{-6} \qquad \text{tensile strain in reinforcement}$$

$$f_{s,t} \coloneqq \epsilon_{s,t} \cdot E_s = 30.93 \cdot ksi \qquad \qquad \text{tensile stress in reinforcement}$$

$$\varepsilon_{uhpc.c} \coloneqq \frac{-2 \cdot \theta \cdot c}{L_{dz}} = -1147 \cdot 10^{-6}$$
 compressive strain in UHPC


$$f_{uhpc.c} \coloneqq \epsilon_{uhpc.c} \cdot \mathrm{E}_c = -9.18 \cdot \mathrm{ksi} \qquad \qquad \text{compressive stress in UHPC}$$


$$d_{gap.min} \coloneqq 2 \cdot \theta \cdot \left\lceil d_{bf} - \left( d_{uhpc} - c \right) \right\rceil = 1.29 \cdot in \qquad \text{minimum required girder end gap}$$


# **Analysis Results**

$$R = \begin{pmatrix} \text{"Analysis Criteria"} & \text{"Actual"} & \text{"Allowable"} & \text{"Design Ratio"} & \text{"Pass/Fail"} \\ \text{"Tensile Strain in UHPC } (\mu\epsilon)\text{"} & 3280.41 & 3500.00 & 1.07 & \text{"Pass"} \\ \text{"Stress in Reinforcement (ksi)"} & 30.93 & 60.00 & 1.94 & \text{"Pass"} \\ \text{"Compressive Stress in UHPC } (\mu\epsilon)\text{"} & -9.18 & -14.00 & 1.53 & \text{"Pass"} \\ \text{"Minimum Girder End Gap (in)"} & \text{"----"} & 1.29 & \text{"----"} & \text{"----"} \\ \end{pmatrix}$$

# **Restoration Plans**







General Ecology - Culverts	Action Summary	NYSDOT Standard Specifications	Special Specifications
Outfall-N-1	Pipe replacement	Section 206 Trench, Culvert, and Structure Excavation	A highway drainage pipe (ex. 24" RCP), Outfall-N-1, that currently outlets into dry swale densely populated with common reed (in triangular interchange area north of Mud Creek/Wetland 10L, where an infiltration or detention basin is proposed) would be reconstructed and extended during HWY ROW reconstruction.
Outfall N-2	Pipe replacement	Section 206 Trench, Culvert, and Structure Excavation, may need Special spec 555.10000006 Abandon Existing Culvert	A highway drainage pipe (ex. 36" CMP), Outfall-N-2, that currently outlets to a steep wet-weather-flow tributary to Mud Creek would be relocated, requiring the construction of a new drainage pipe. There is erosion downstream of the existing outfall; the Design-Builder shall conduct a H&H analysis to ensure no erosion will occur downstream of the new drainage pipe and/or install outfall protection, an energy dissipator, and/or possibly lightly reinforce the ex channel downstream of the outfall. Coordination with the Geotechnical Consultant is recommended.
Culvert E-41	Culvert extension	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	Design-Builder shall extend the existing triple barrel culvert structure 10 feet downstream into the unnamed tributary to North Branch Ley Creek, creating 134 linear feet of additional culvert and reducing the creek length to 40 linear feet, and reduce the surface water area to 400 square feet. The extended culvert outfall shall include an energy dissipator or similar to protect the streambed downstream of the culvert from erosion. NYSDEC specifies that the width of the structure shall be 1.25 times the normal width of the streambed. The overall culvert capacity should be able to accommodate expected high flows.  There is a special spec for extension of a CMP culvert with a paved invert; this could be potentially be modified for this culvert (603.07911806)
Culvert E-31	Culvert extension	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	Design-Builder shall extend culvert by 20 feet into the upstream wetland area. NYSDEC specifies that rip rap shall be used as head wall protection to prevent scouring around the inlet and outlet of the culvert.
Culvert N-6	Replace with Open Bottom Culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam, Section 620 Bank and Channel Protection	Design-Builder shall extend culvert by 21 feet to connect with the existing wetland; at minimum, the culverts must have a width at bankfull (1.25 x Bankfull width) and would be embedded at least 20 percent at the inlet
Culvert N-8	Replace with Open Bottom Culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam, Section 620 Bank and Channel Protection	The Design-Builder shall extend the culvert by 64 feet to accommodate the new HWY ROW and safely convey the South Branch of Pine Grove Brook; at minimum, the culverts must have a width at bankfull (1.25 x Bankfull width) and would be embedded at least 20 percent at the inlet
Culvert N-9	Replace with Open Bottom Culvert	Section 206 Trench, Culvert, and Structure Excavation	The Design-Builder shall replace the existing culvert with an open bottom culvert, and extend the length by 75 feet into the triangular interchange area to accommodate the new highway geometry
Culvert N-14	Demolish ramp, ramp embankment, and 98 feet of existing culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 555.10000006 Abandon Existing Culvert	The Design-Builder shall remove the existing ramp and culvert and grade the areas in order to implement the Restoration Plan. Culvert N-14 is currently 234 linear feet, 98 linear feet of which would be removed from the demolition area (the remainder of the pipe is needed to maintain drainage patterns under the remaining HWY ROW ramp.)
Culvert N-15	Demolish ramp, ramp embankment, and existing 90 foot Culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 555.10000006 Abandon Existing Culvert	The Design-Builder shall remove the existing ramp and 80 foot long culvert and grade the areas in order to implement the Restoration Plan.
Culvert N-20	Replace with Open Bottom Culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	The Design-Builder shall replace the existing culvert with an open bottom culvert. At minimum, the culvert must have a width at bankfull (1.25 x Bankfull width) and would be embedded at least 20 percent at the inlet. Design-Builder shall use H&H modeling to ensure sufficient capacity for bankfull storm event and flood events. Current culvert sizes may be too small. Inlets and outlets need to be embedded in the embankment and protected with riprap to prevent scour - H&H modeling will help determine erosive forces and extent of protection needed. Any area disturbed during construction shall be stabilized after.
Culvert N-21	Replace with Open Bottom Culvert, further downstream from original culvert, to accommodate new ROW geometry	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	The Design-Builder shall replace the existing culvert with an open bottom culvert. At minimum, the culvert must have a width at bankfull (1.25 x Bankfull width) and would be embedded at least 20 percent at the inlet. The Design-Builder shall shift the Culvert N-21 downstream. The open bottom culvert would be 6 feet longer than the existing culvert. It would result in a decrease in length to the section of Mud Creek between N-21 and N-20, which is currently 839 linear feet (0.40 acres) and would be reduced to 795 linear feet (0.38 acres). This would result in a 44 linear foot decrease in length, or 0.02 acres of surface water.
Culvert N-23 and N-21	Bridge and retaining wall construction	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	The Design-Builder shall construct a new bridge between the existing N-23 and N-21 culverts. The Design-Builder shall avoid bridge construction in any portions of Mud Creek and shall avoid raising the floodplain where possible.

Culvert N-23	Replace with Open Bottom Culvert	Section 206 Trench, Culvert, and Structure Excavation, Special spec 553.010001 Coffer Dam	The Design-Builder shall replace the existing culvert with an open bottom culvert of equal length. At minimum, the culvert must have a width at bankfull (1.25 x Bankfull width) and would be embedded at least 20 percent at the inlet. Design-Builder shall size culverts using H&H modeling to ensure sufficient capacity for bankfull storm event and flood events. Current culvert sizes may be too small. Inlets and outlets need to be embedded in the embankment and protected with riprap to prevent scour - H&H modeling will help determine erosive forces and extent of protection needed. Any area disturbed during construction shall be stabilized after.
Floodplain Restoration associated with removal of existing ramp, ramp embankment, and culverts N-14 and N-15	Restore 2.0 acres of floodplain associated with a tributary to Mud Creek associated with Culverts N-14 and N-15)	Section 610 - Ground Vegetation - Preparation, Establishment and Management (All subsections except 1.02, 1.03, 1.12, 1.13, 2.03, 2.05, 2.12, and 2.13); Section 611 - Planting, Transplanting And Post Planting Care; Section 713 Landscape Development Materials	The Design-Builder shall develop a Restoration Plan for wetland, channel, and floodplain areas that would be temporarily disturbed during construction and/or for the channel and floodplain areas that have been identified for restoration. One section of the Restoration Plan shall include the restoration of the floodplain. At minimum, 2.0 acres of floodplain would be restored. The Design-Builder shall identify a reference floodplain and justification for its use and present it to NYSDEC for review and approval. One of the goals and objectives will be to grade the land to fully reconnect the adjacent wetland. The Restoration Plan shall establish goals and objectives as part of the Restoration Plan for review and approval by NYSDEC. At minimum, the entire restoration area shall be seeded at a rate specified by 610-3.04. Plugs and vines and groundcovers shall be planted at a rate of 1 plant per 4 sq. feet. Trees and shrubs at a rate of no less than 350 bare root plants per acre. At minimum, herbaceous plugs shall be spaced no more than 18" apart. The Design-Builder shall develop a Monitoring and Adaptive Management Plan as part of the development of the Restoration Plan. The Design-Builder shall follow all permit conditions outlined in the NYSDEC/USACE permits, including the Performance Standards established as part of the Monitoring and Adaptive Management Plan. At minimum, the Performance Standards shall stipulate that plant survival shall not be less than 85% after the five-year monitoring period. Invasive species (specifically Phragmites australis) shall not exceed 5% at the end of the five-year monitoring period.
Culvert N-22	Remove culvert and restore 250 feet of Mud Creek and associated wetland	Section 610 - Ground Vegetation - Preparation, Establishment and Management (All subsections except 1.02, 1.03, 1.12, 1.13, 2.03, 2.05, 2.12, and 2.13); Section 611 - Planting, Transplanting And Post Planting Care; Section 713 Landscape Development Materials; Special spec for fine channel grading (from Gay's Point project)	The Design-Builder shall develop a Restoration Plan for wetland, channel, and floodplain areas that would be temporarily disturbed during construction and/or for the channel and floodplain areas that have been identified for restoration. One section of the Restoration Plan will include the channel and riparian buffer restoration of Mud Creek. Mud Creek channel restoration will mimic an upstream portion of Mud Creek. The Design-Builder shall select a reference condition and justification for its use as part of its development of the Restoration Plan and the Restoration Plans goals and objectives. Only native species, including native aquatic plants, shall be used in the restoration plan. The Design-Builder shall submit the restoration plan to NYSDEC for approval. The vegetated buffer shall have a minimum width of 50° where space is limited and shall follow the Three Zone Concept outlined in NYSDEC Riparian Buffers guidance (https://www.dec.ny.gov/chemical/106345.html). Where possible, the vegetated buffer shall be 100° wide to meet NYSDEC's riparian corridor guidance. The Design-Builder shall develop a Monitoring and Adaptive Management Plan as part of the development of the Restoration Plan. The Design-Builder shall follow all permit conditions outlined in the NYSDEC/USACE permits, including the Performance Standards established as part of the restoration monitoring plan. At minimum, the Performance Standards shall stipulate that plant survival shall not be lower than 85% after the five year monitoring period and shall not be lower than 85% for three or more consecutive years within the five year period. Invasive species (specifically Phragmites australis) shall not exceed 5% at the end of the five year monitoring period.

Floodplain restoration	Restore 1.6 acres of floodplain adjacent to mainstem	Section 610 - Ground Vegetation - Preparation, Establishment and Management	The Design-Builder shall develop a Restoration Plan for wetland, channel, and floodplain areas that would be
associated with removal of	of Mud Creek	(All subsections except 1.02, 1.03, 1.12, 1.13, 2.03, 2.05, 2.12, and 2.13); Section	temporarily disturbed during construction and/or for the channel and floodplain areas that have been identified for
Culverts N-21 and N-22 and		611 - Planting, Transplanting And Post Planting Care; Section 713 Landscape	restoration. One section of the Restoration Plan shall include the restoration of the floodplain. At minimum, 1.6 acres of
associated existing highway		Development Materials	floodplain would be restored. The Design-Builder shall identify a reference floodplain and present the reference
embankments			floodplain to NYSDEC for review and approval. One of the goals and objectives will to grade the land to fully reconnect
			the adjacent wetland. The Restoration Plan shall establish goals and objectives as part of the Restoration Plan for
			review and approval by NYSDEC. At minimum, the entire restoration area shall be seeded at a rate specified by 610-
			3.04. Plugs and vines and groundcovers shall be planted at a rate of 1 plant per 4 sq. feet. Trees and shrubs at a rate of
			no less than 350 bare root plants per acre. At minimum, herbaceous plugs shall be spaced no more than 18" apart. The
			Design-Builder shall develop a Monitoring and Adaptive Management Plan as part of the development of the
			Restoration Plan. The Design-Builder shall follow all permit conditions outlined in the NYSDEC/USACE permits, including
			the Performance Standards established as part of the Monitoring and Adaptive Management Plan. At minimum, the
			Performance Standards shall stipulate that plant survival shall not be lower than 85% after the five year monitoring
			period and shall not be lower than 85% for three or more consecutive years within the five year period. Invasive species
			(specifically Phragmites australis) shall not exceed 5% at the end of the five year monitoring period.
1			

<b>Hazardous Was</b>	te Contaminated	<b>Materials</b>	Additional	Information
----------------------	-----------------	------------------	------------	-------------



95 Perry Street Suite 300

120 East Washington Street Suite 414 Syracuse, NY 13202

325 Gold Street Suite 701 Brooklyn, NY 11201



#### Memorandum

To: File

From: Justin Kellogg, M.S., QEP, Senior Environmental Engineer

Date: May 12, 2022

Subject: I-81 VIADUCT PROJECT - PHASE 1, CONTRACT 1

PIN 3501.90. Contract D900054

Hazardous Waste/Contaminated Materials Additional Information for Contract 1 RFP

Watts Project Number 13092

The purpose of this Memorandum is to identify additional information that would assist in the bidding process for the I-81 Viaduct Project - Phase 1, Contract 1 Request for Proposal (RFP).

Hazardous waste/contaminated materials assessments have identified those properties where either contaminated soils and groundwater or underground storage tanks primarily used for petroleum sales are suspected to be present. Information describing the specific sites of concern is found in the Hazardous Waste/Contaminated Materials Screening Assessment Report dated February 2020 and the stand-alone Phase I Environmental Site Assessment for Proposed Noise Walls 16 A/B Memorandum dated May 17, 2021. The aforementioned documents were prepared for a larger project footprint than the Contract 1 project limits. This Memorandum identifies the sites of potential environmental concern that are found within or adjacent to the Contract 1 project limits. Please refer to the abovementioned documents for additional information on the sites of potential environmental concern.

The 18 sites in the table below are in the vicinity of the Design-Build Contract 1 project corridor and were identified as potentially contaminated; however, only one site (3.2.5, CSX: DeWitt Railroad Yard - shown in bold below) is considered to have a high probability of contamination being present.

The 17 other sites in the table below are considered to have a low probability of contamination and are called out as an advisory that the Design-Builder should be on the lookout and aware of the potential for contamination in the vicinity of these sites.

Site ID #	Property Name and Address	Current or Former Use	Potential Environmental Concerns	Notes
3.1.1	I-81: Sutton Dr - I-481 Interchange & I- 481: I-81 Interchange - Northern Blvd	Roadway Corridor	Petroleum Contamination	Roadway corridor, spills are too scattered to identify them specifically.

# Watts Architects &Engineers

I-81 VIADUCT PROJECT - PHASE 1, CONTRACT 1 PIN 3501.90, Contract D900054 Hazardous Waste/Contaminated Materials Additional Information for Contract 1 RFP Watts Project Number 13092

Site ID	Property Name and Address	Current or Former Use	Potential Environmental Concerns	Notes
3.1.2	Burdick Auto Dealer: 5947 Circle Dr	Automobile Related	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Noise barrier installation disturbance is within the ROW and close to highway. Contamination, if present, is likely off the ROW.
3.1.3	Burdick Auto Dealer: 5857-5927 Circle Dr	Automobile Related, USTs	Petroleum Contamination, USTs	Soil disturbance is within the highway ROW and likely tank/spill sites are far from the ROW.
3.1.4	National Grid: 7496 Round Pond Rd	Natural Gas Fueling Station	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Disturbed area is within the ROW. Past spills were off of the highway ROW, small and mostly cleaned/closed.
3.1.5	Swift Transportation: 7470 Round Pond Rd	Automobile Related, USTs	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Soil disturbance is within the highway ROW and likely tank/spill sites are far from the ROW.
3.1.6	Monroe Tractor & Implement: 7300 Eastman Rd	Automobile Related	Petroleum Contamination	Soil disturbance is within the highway ROW and likely spill sites are far from the ROW.
3.1.7	Lan-Co Companies: 7330 Eastman Rd	Solid Waste Landfill	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Soil disturbance is within the highway ROW and likely spill sites are far from the ROW.
3.2.1	I-481: I-90 - Route 592 Interchange	Roadway Corridor	Chemical/Solvent Contamination, Petroleum Contamination	Roadway corridor, spills are too scattered to identify them specifically.
3.2.2	Inficon Inc: 2 Technology Pl	Manufacturing Facility and USTs	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Soil disturbance is within the highway ROW and likely tank/spill sites are far from the ROW.
3.2.3	Joy Process Mechanical 6747 Benedict Rd	Manufacturing Facility	Chemical/Solvent Contamination	Edge of disturbance area, but no ROW takes and started in 1986 (farmed prior) and no tanks.
3.2.4	Ultra Dairy: 6750 Benedict Rd	Manufacturing Facility and USTs	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Edge of disturbance area, but no ROW takes and tanks are ASTs, few, and somewhat recent.

**Watts** 



I-81 VIADUCT PROJECT - PHASE 1, CONTRACT 1 PIN 3501.90, Contract D900054 Hazardous Waste/Contaminated Materials Additional Information for Contract 1 RFP Watts Project Number 13092

Site ID #	Property Name and Address	Current or Former Use	Potential Environmental Concerns	Notes
3.2.5	CSX: DeWitt Railroad Yard	Railroad	Chemical/Solvent Contamination	Bridge will be renovated, recommend investigative soil borings near piers and abutment excavations (to depth of excavation). Contaminated soil assumed to be encountered.
3.2.6	Penske Truck Rental: 6755-6773 Manlius Center Rd	Automobile Related, USTs	Petroleum Contamination, Abandoned USTs	Edge of disturbance area, but tanks were likely near the building, and I-481 is elevated (for the bridge crossings) in comparison to this site.
3.2.7	84 Lumber: 6801 Manlius Center Rd	Lumber Yard and USTs	Chemical/Solvent Contamination, Petroleum Contamination, Abandoned USTs	Edge of disturbance area, but no ROW takes, there is a substantial drainage ditch between the property and roadway, and I-481 is quite elevated (for the bridge crossings) in comparison to this site.
3.2.8	Allied Spring & Services Inc: 6800 Manlius Center Rd	Automobile Related, USTs	Chemical/Solvent Contamination, Petroleum Contamination	No ROW takes and construction not adjacent.
3.2.9	B&C Self- Storage: 5991 Drott Dr	Automobile Related, USTs	Petroleum Contamination, Abandoned USTs	Construction is within ROW and not adjacent to this site. Contamination, if present, is likely off the ROW.
А	Residential Property 434 Garden Center Drive	Automobile Related	Petroleum Contamination, Abandoned USTs	Construction of noise barrier is on the embankment above grade from house. Contamination, if present, is likely off the ROW.
В	Mattydale Shopping Plaza 2803 Brewerton Rd	Automobile Related	Petroleum Contamination, Abandoned USTs	Construction of noise barrier on embankment above grade from and somewhat far from the shopping plaza. Contamination, if present, is likely off the ROW.

## Notes:

- 1) Site ID #s 3.1.1 through 3.2.9 in the table above refer to the sites identified within the Hazardous Waste/Contaminated Materials Screening Assessment Report dated February 2020.
- 2) Site ID #s A and B in the table above refer to the sites identified within the Phase I Environmental Site Assessment for Proposed Noise Walls 16 A/B Memorandum dated May 17, 2021.
- 3) Bold in the table above highlights the CSX: Dewitt Railroad Yard where it is assumed that contaminated soil will be encountered.