Parking Lot Electric Vehicle References

Parking Lot Power Requirements


•Con Edison Electrical Requirements:

- i. Approximately 1250 KVA of service
- ii. Approximately 1,200 amps for the 4 DC fast chargers (480 volts each) and approximately 600 amps for 20 Level 2 chargers (208/220 volts).

Parking Lot Power Feeder Diagram

Line Diagram for Electric Vehicle Charging Station - Power Fed from Con Ed (Assuming 120/208V, 3 Phase service)

- (4) Units of DC Fast Charger Station, 150KW, 480V, 3 Phase
- (20) Units of Level 2 EV Charger Station, 7.2Kw, 240/208V, Single Phase




Transformer (For Reference Only)

DESCRIPTION 1 Bolted Cover w/ Nutquard 2 Cooling Corrugate 3 Cooper Bayonet Fusing w/ Dripshield 4 Current Limiting Backup Fuses (Internal) 5 Delta Wye Switch 6 Drain Valve with Sampler 7 Ground Pad .50-13 Tap 8 Ground Strap and Pad 9 Ground Strap and Pad 10 H0 Bushing 11 6.0kV (5.1kV MCOV) Elbow Arrester 12 High Security Cabinet w/ 1 Pentahead Door Bolt per door 13 35kV 200 Amp HV Bushing Well w/ 15kV Insert 14 Lifting Lug 15 Liquid Temperature Gauge 16 1.2kV LV Bushing w/ 6 Hole Spade 17 Magnetic Oil Level Gauge 18 Nameplate 19 One Inch Upper Press. Conn. and Fill Plug 20 Parking Stand 21 Pressure Relief Valve 22 Pressure Vacuum Gauge 23 Tank Base w/ Jacking and Rolling Facilities 24 5-Position Tap Changer 25 X0 Bushing

2.0 17.0 Pad Opening 65.0 Pad Opening Тур Тур 10 (20) (25) (13) (16) 4.3 Typ € HZB 72.00 44.0 36.0 0 0 6 30.25 68.00

Cabinet Removed



MATERIAL:

ALL DIMENSIONS ARE IN INCHES [MM]

THE INFORMATION ON THIS DOCUMENT WAS CREATED BY EATON. IT WAS DISCLOSED IN CONFIDENCE AND IS ONLY TO BE USED FOR THE PURPOSE IN WHICH IT WAS SUPPLIED.

THIS DRAWING HAS BEEN GENERATED FROM A 3D MODEL.

Powering Business Worldwide

тіть: Distribution Transformer Outline Drawing

DESC: COOPER POWER SERIES THREE-PHASE PAD-MOUNTED COMPARTMENTAL TYPE

D10NVRYW

REVISIONS

3PH Padmount Transformer 60Hz 1000.0 kVA ONAN 65 AWR Mineral Oil HV 4800/8320Y/4800 75 kV BIL LV 480Y/277 30 kV BIL 5.74 %IZ

Approximate Weight 7659 lbs. Munsell Green Topcoat Mild Steel Construction

DESIGN #: 1


Typical Transformer Pad Details (For Reference Only)

Flat Pads-Sizing for Three Phase Transformers

NYSEG **DISTRIBUTION STANDARDS** (Underground)

SECTION 7 - MANHOLES, VAULTS & PADS

FLATPAD SELECTION GUIDE FOR PADMOUNTED UTILIZATION AND STEP **TRANSFORMERS**



		Γ	IMENSION	S OF I	OURE	OR P	RECAS	T CON	CRETE	PADS		
	TRAN	RATING		DIMENSIONS IN INCHES								
TYPE	KV	PHASE	KVA	A	В	С	D	E	F	G	WEIGHT	SS#
Util.	15/35	1	25-167*	50	50	24	12	7	13	13	750	262-803-00
Util.	15	3	75-750**	78	72	48	18	10	17	13	2700	262-777-00
Util.	15	3	750-2500	89	75	50	17	14	21	18	3100	262-781-00
Util.	35	3	75-1500	89	75	50	17	14	21	18	3100	262-781-00
Util.	35	3	2500	96	96	60	24	12	24	12	4300	262-782-00
Step		1/3	250-500	76	71	30	15	22.5	23	23	2600	262-790-00
Step		3	500-1500	95	89	43	17	20	26	26	4100	262-791-00
Step	†	1 3	1500-2500	96	96	62	17	20	17	17	4300	262-792-00
Step		3	3750-5000	120	120	80	24	20	20	20	6500	262-793-00

^{*} Used for conversion of a submersible transformer installation to a padmounted installation. This unit is 4" thick,

Notes

- 1. Reinforce with grade 60 #4 bars on 6" centers both ways
- 2. 4000 PSI concrete at 28 days
- 3. Top and Bottom to be smooth finish

FLAT PADS

ISSUE NO. 5 DATE: JUNE 2003 DR. KLH CKD. RSE APPR. RSE

3.1

This is a NYSEG distribution standard. References to page and section numbers within this standard are to other NYSEG standards not to page and section numbers within this book.

^{** 750}KVA will fit on both this pad and SS# 262-781-00. Use the larger pad where transformer size may be increased in the future




	TABLE														
THREE PHASE TRANSFORMER		CONCRETE PAD TYPE OF	DIMENSIONS (INCHES)								APPROX. CONC. VOL.	APPROX. PRECAST PAD WEIGHT (LBS.)			
SIZE (KVA)	PRIMARY VOLTAGE	INSTALLATION	Α	В	С	ə	E	F	G	Н	T	X	(CU. YDS.)	REINF.	PAD
	4KV & 13KV	FIELD POURED	72	19				44	20		8 1/2	3	0.95		
75-500	4KV & 13KV	PRECAST	72	19	9	30	9	44	20	12	7 1/2	2	0.84	212	3395
75-500	27KV	FIELD POURED	72	22				44	20		8 1/2	3	0.93		
	2/NV	PRECAST	72	22	8	27	3	44	20	12	7 1/2	2	0.82	207	3308
	4104 0 47104	FIELD POURED	84	19				58	13		8 1/2	3	1.05		
1000-2000	4KV & 13KV	PRECAST	84	19	8	36	15	58	13	10	7 1/2	2	0.96	233	3876
	27KV	FIELD POURED	84	22				58	13		8 1/2	3	1.05		
	2/NV	PRECAST	84	22	8	33	15	58	13	10	7 1/2	2	0.93	226	3767

SECTION A-A

MATERIAL SPECIFICATIONS:

CONCRETE SHALL CONFORM TO CON EDISON SPEC. EO-1008, CLASS II.
CEMENT MORTAR SHALL CONFORM TO CON EDISON SPEC. EO-100,167 (STK # 000-0208).
ALL REINFORCING BARS SHALL BE BILLET STEEL, DEFORMED, AND SHALL CONFORM
TO ASTM SPEC. DES. A-B15, GRADE 60.
ALL REINFORCING BARS SHALL BE EPOXY COATED AND SHALL CONFORM
TO ASTM SPEC. DES. A-775.

TOOL FINISH EDGE

ALL AROUND

STRUCTURAL STEEL SHALL CONFORM TO ASTM SPEC. DES. A-36. WELD STRUCTURAL STEEL MEMBERS IN ACCORDANCE WITH EO-11320.

CONSTRUCTION SPECIFICATIONS:

REINFORCING BARS SHALL BE WIRE TIED AT ALL CONTACT POINTS WITH PLASTIC COATED

ALL REINFORCING BARS SUPPORTED FROM FRAMEWORK SHALL REST ON COATED WIRE BAR SUPPORTS. EPOXY COATING, DAMAGED AS A RESULT OF HANDLING OR CUTTING OF REINFORCING BARS, SHALL BE REPAIRED WITH PAICHING MATERIAL COMFORMING TO ASTM SPEC. DES A-775.

SHALL BE REPAIRED WITH PAIGHING MALERIAL COMPORMING TO ASIM SPEC. DES A-775.

A 2" MINIMUM OF CONCRETE SHALL BE MAINTAINED OVER ALL REINFORCING BARS AND SHAPES, UNLESS OTHERWISE NOTED.

WHERE MAIN HORIZONTAL BARS ARE CUT FOR REPLACEMENT PURPOSES, SPLICE BARS OF THE SAME SIZE AND AT LEAST 2'-6" LONG SHALL BE INSTALLED ACROSS THE CUT POSITION.

PAD SHALL BE INSTALLED ON A MINIMUM OF 6" CRUSHED STONE.


TOP SURFACE OF PAD SHALL HAVE A STEEL TROWEL FINISH.

TOP OF PAD SHALL BE 6" ABOVE GRADE.

OMIT LIFTING EYES, POCKETS AND DRAIN HOLES FROM FIELD CONSTRUCTED PADS.

FILL LIFTING HOLES AND OPEN AREAS AROUND CONDUITS WITH MORTAR AFTER PAD IS INSTALLED.

Drawing For Reference Only**



SECTION B-B

REF. SPECS:

INSTALLATION OF PAD AND CONDUIT_ _ _ _ _ _ _ EO-12482-B THREE PHASE, METAL ENCLOSED, PAD MOUNTED XFORMERS

REQUIREMENTS FOR THE INSTALLATION OF SINGLE AND THREE PHASE PAD MOUNTED TRANSFORMERS.

占

_ _EO-6229

THIS DWG. SUPERSEDES DWG. E0-12180-C, E0-12541-C, E0-13757-C

CONCRETE PAD FOR 3 PHASE PAD MOUNTED

TRANSFORMERS CONSOLIDATED EDISON COMPANY OF N.Y., INC.

DISTRIBUTION ENGINEERING DEPT.

1/29/70 DWG. EO-13775-B REV. 7 LAST REV.4/6/05

TRANSFORMERS FIELD MANUAL NO.22: SECTION 8:

FIELD MANUAL NO.24:

SECTION 8:

TRANSFORMERS

CONSTRUCTION STDS MANUAL NO.3: SECTION 37:

SUBWAY


THREE PHASE PADMOUNT TRANSFORMER CONCRETE PAD SPECIFICATIONS

NOTES:

- 1. SEE FIG. 3 FOR ADDITIONAL REQUIREMENTS, SPECS. AND CLEARANCE REQUIREMENTS.
- 2. OPENING TO BE D X F DIMENSIONS (AFTER FORM IS REMOVED).
 3. CRUSHED STONE ±3'-0' BENEATH PAD.
- 4. 6" X 6" X 6/6 WIRE MESH.
- 5. NUMBER OF SECONDARY CONDUITS TO CUSTOMERS EQUIPMENT TO SUIT LOAD AND SITE CONDITIONS.
- 6. CONDUITS NOT TO EXTEND ABOVE PAD.
- 7. PAD SHALL BE LEVEL AND ALL EDGES CHAMFERED.
- 8. WHEN REQUIRED, TWO (2) PRIMARY CONDUITS IN THIS AREA.
- 9. SECONDARY CONDUITS NOT TO EXCEED "I" DIMENSION.
- 10. PRIMARY CONDUITS SHALL BE WITHIN DIMENSION H. 11. ALL PAD DIMENSIONS ARE THE FINISHED PRODUCT, AFTER ALL FORMS ARE REMOVED.
- 12. WARNING: DO NOT PULL IN ANY PRIMARY OR SECONDARY WIRES. YOU MUST WAIT FOR THE TRANSFORMER TO BE DELIVERED.

PAD DIMENSIONS

TRANSFORMER SIZE-KVA	Α	В	С	D	E	F	G	Н	I
75-500	8′-6″	7′-3″	12"	13"	16"	42"	24"	12"	18"
750-1000	9'-0"	7′-8 ″	12"	18"	10"	42"	30*	12"	24"
1500-2500	11'-0"	9'-2"	18"	18"	10"	42"	42"	12"	24"





28 Pad Construction Detail

Figure 10.40: Three-Phase Padmounted Transformer – Type II-A (Concrete)





Figure 27.0-2 15kV Transformer Pad 750- 2500kVA 44-114 (ref-44-114/UF8B)




11.0 Transformer Mechanical Protection/Bollards


Whenever possible, equipment should be located so it is not subject to vehicular damage. If this is not feasible, adequate guards such as concrete filled pipes (Bollards) shall be placed to protect the equipment.

Bollards shall consist of 6 inch minimum diameter hot dip galvanized or painted steel pipes filled with concrete. When Bollards can not be painted at the time of installation, painted covers shall be installed. Page 56 shows manufacturer. Bollards are to be 5 feet above the ground and a minimum of 4 feet below the ground. Bollards to be set in a concrete footing as shown in detail below. Concrete is to be crowned on top of all bollards. Bollards shall be installed with due care to avoid interfering with ground grid and conduits. Refer to Pages 37 thru 40 for Transformer Pad dimensions. For switchgear locations, see pages 34 and 35.


The number, type (galvanized or steel) and locations of bollards shall be determined by Distribution Design/Planning, taking into account proximity to traffic and to buildings as well as other barriers to traffic. Other factors such as salt spray and fertilizers may impact type of bollard required. Suggested bollard locations and dimensions are shown below. The location of bollards shall not impede a door opening of 100 degrees.







Blow up drawing detailing this is located on page 44







Picture of Bollard cover, use for when Bollards can not be painted.


Notes

- 1. Six foot minimum clearance from front of pad.
- Distribution Design/Planning shall designate the number and location of Bollards by marking the Bollards of this drawing as follows:
- Bollards shall be supported with a 12" minimum diameter concrete footing 6" below grade to base of the bollard.
- For installations around oil containment curbs, install bollards six feet minimum on all applicable sides.



10' Clear Space From Front Of Pad





SHEET 3 OF 3

NOTES:

- 1. THE CUSTOMER WILL NORMALLY PROVIDE THE PAD FOR THREE PHASE PAD-MOUNTED TRANSFORMERS. THE STANDARD IS INTENDED AS A GUIDE FOR PROVIDING THE SPECIFICATIONS FOR PAD INSTALLATIONS APPLICABLE TO PAD-MOUNTED TRANSFORMERS OF VARIOUS KVA SIZE AND DIMENSIONS. THE STANDARD INSTALLATION USES A PRE-CAST CONCRETE BASE AND COVER. THE CONCRETE BASE IS OF UNIFORM SIZE AND UTILIZES COVERS WITH DIFFERENT SIZED WINDOW OPENINGS TO ACCOMMODATE THE KVA SIZE OF THE PAD-MOUNTED TRANSFORMER. DETAILED SPECIFICATIONS AND INSTALLATION REQUIREMENTS ARE PROVIDED IN PAGES 1 TO 3 OF THIS STANDARD.
- 2. THE SIDES AND REAR OF THE PAD SHALL BE A MINIMUM OF TEN (10) FEET FROM THE WINDOWS AND FIRE ESCAPES AND A MINIMUM OF THREE (3) FEET (TEN (10) FEET PREFERRED) FROM ALL BUILDINGS, FENCES, OR OTHER OBSTRUCTIONS WHICH WILL IMPEDE THE FREE FLOW OF COOLING AIR AROUND THE TRANSFORMER. THE FRONT OF THE PAD (WINDOW SIDE) SHALL HAVE A MINIMUM OF TEN (10) FEET OF UNOBSTRUCTED WORKING SPACE.
- 3. ACCESS TO PAD AREA BY VEHICLE MUST BE POSSIBLE AT ALL TIMES TO INSURE PROPER OPERATION AND MAINTENANCE FUNCTIONS.
- 4. STONE FOR BASE AND SIDES OF THE BOX PAD SHALL BE 3/4" MINIMUM TO 1-1/2" MAXIMUM CRUSHED ROCK OR WASHED STONE. 1/2" CRUSHED ROCK OR WASHED STONE MAY BE USED FOR TOP 6" IN LOCATIONS WHERE WINDOW BREAKAGE MAY BE A PROBLEM. FOR THE BASE, STONE SHALL BE PLACED ON UNDISTURBED OR WELL TAMPED EARTH.
- 5. AREA AROUND THE BOX PAD SHALL BE GRADED SO THAT SURFACE WATER WILL DRAIN AWAY FROM CRUSHED STONE OIL CONTAINMENT.
- 6. THE BOX PAD SHALL BE INSTALLED SUCH THAT THE TOP SURFACE IS LEVEL TO WITHIN 1/4" HIGH TO LOW.
- 7. IN GENERAL, 5" CONDUIT SHOULD BE USED FOR BOTH PRIMARY AND SECONDARY CONDUCTORS. HOWEVER, THE SECONDARY CONDUIT SHOULD BE SIZED ACCORDING TO THE SECONDARY CONDUCTORS BEING INSTALLED.
- 8. PERMANENT SUPPORT SHALL BE PROVIDED FOR THE SECONDARY CONDUCTORS SUCH THAT THE TOTAL WEIGHT SUPPORTED BY EACH TRANSFORMER BUSHING SHALL NOT EXCEED TEN POUNDS. THUS SINGLE RUNS OF 500 MCM COPPER AND LARGER, 1000 MCM AL AND LARGER AND PRACTICALLY ALL MULTIPLE CONDUCTOR RUNS NEED TO BE SUPPORTED TO LIMIT THE STRESS ON THE BUSHINGS.
- 9. CENTRAL HUDSON RESERVES THE RIGHT TO REQUIRE SUITABLE BARRIERS IN TRAFFIC AREAS TO REDUCE THE PROBABILITY OF DAMAGE DUE TO TRUCKS, AUTOMOBILES, CONSTRUCTION EQUIPMENT, AND THE LIKE. SUITABLE BARRIERS MIGHT BE 4" (MINIMUM) STEEL PIPE, FILLED WITH CONCRETE, SET 4 ft. DEEP AND EXTENDING 3 TO 4 FEET ABOVE GROUND. BARRIERS SHOULD BE SET BEYOND THE OIL CONTAINMENT IN LOCATIONS WHICH WILL INTERCEPT VEHICLES YET NOT INTERFERE WITH THE INSTALLATION OR REMOVAL OF THE TRANSFORMER.
- 10. ALL GROUNDING MUST BE IN ACCORDANCE WITH COMPANY SPECIFICATIONS.
- 11. SIZE THE GROUNDING ELECTRODE CONDUCTOR AS FOLLOWS:
 - A. 200A SECONDARY SERVICES: #4 AWG.
 - B. 400A SECONDARY SERVICES: #1/0 AWG.
 - C. LARGER THAN 400A SECONDARY SERVICES: #3/0 AWG.

ELECTRIC STANDARDS	CENTRAL HUDSON GAS & ELECTRIC CORP.	DATE 5-1-15
DRWN.	TUDEE DUACE DAD ODECTETOATIONS	ISSUE
DSGN.	THREE PHASE PAD SPECIFICATIONS 5-34.5 KV	APP.
APPD.	75-2000 KVA	APP.

Switchboard (For Reference Only)

ACCESS TO	: Front Only	PHASE:	3P4W	CONSOLIDATED EDISON NY. Spec. 377
CLASS:	2	AMPERE	: 1200A	CODE C3
LABEL:	U/L SE	BUS MTL	:	C/T TYPE Window
VOLTAGE:	480/277V	PLATE:	Tin Plate	P/T TYPE
STYLE:	Bolt-On	RATING:	Fully Rated	
BUS BRACIN	NG (RMS SYM):	65000A	PER GE DWG <u>75C143992 PV44</u>
DEV.MIN.INT.R	ATING (RMS SY	M):	65000A	PER PWR CO SPEC. 75C143991 SH. 42

Switchboard / Device Information

Circuit No.	Device	Amps	s Poles	Nameplates	Lugs/Cable Size	Notes
Main	SKLC12	1200	3			11,12,13,14,15
1	FBN6	15	1		(1) - #14 - #10 AWG CU - Mech. AL	
2	SGLA4	350	3		(2) - 2/0 - 250 MCM CU - Mech. AL	
3	SGLA4	350	3		(2) - 2/0 - 250 MCM CU - Mech. AL	
4	SGLA4	350	3		(2) - 2/0 - 250 MCM CU - Mech. AL	
5	SGLA4	350	3		(2) - 2/0 - 250 MCM CU - Mech. AL	


NOTES:

1. Switchboard furnished with a rainproof TYPE 3R (non-walk-in) enclosure.


NOTE: See plan view for details. Need additional 1 inch space clearance on top and 1.5 inch clearance on the rear of the swbd.


- 2. Equipment ground bus furnished with lugs.
- 3. Switchboard furnished with Portable Test Set GTUTK20.
- 4. Switchboard furnished with Nameplates.
- 5. All Nameplates to be fastened with screws.
- 6. Shipping splits between each section, ship each section separately.
- 7. Switchboard furnished with bottom floor plates.
- 8. Switchboard furnished with section space heaters.
- 9. Switchboard furnished with thermostat control for section space heaters.
- 10. Switchboard furnished with fully rated panel.
- 11. Device furnished with MET (LSIG) programmer.
- 12. Device is furnished with integral ground fault protection.
- 13. Device is furnished with RELT (Reduced Energy Let Through).
- 14. Device furnished with padlocking provisions.
- 15. Device requires RELT or ZSI feature if Authority having jurisdiction has adopted NEC 2014 code requirements.
- 16. Estimated total factory connected wiring points for the lineup 36.
- 17. Estimated shipping weight for the lineup is 2454 lbs.

PROJECT NAME :	DWG TITLE:	CREATED BY:	Sherif, Tarek	PRODUCT NAME:
NYPA EVI SWBD	Device	CHECKED BY:		Spectra Series
CUSTOMER:	Information	APPROVED BY:		Specifa Series
ABB INC, CARY		DATE: 6/8/2	019 2:09:21 AM	Switchboard
	1	DEVIOLONI NIO		



ACCESS TO	: Front Only	PHASE:	3P4W	CONSOLIDATED EDISON NY. Spec. 377
CLASS:	2	AMPERE	: 1200A	CODE C3
LABEL:	U/L SE	BUS MTL	:	C/T TYPE Window
VOLTAGE:	480/277V	PLATE:	Tin Plate	P/T TYPE
STYLE:	Bolt-On	RATING:	Fully Rated	
BUS BRACI	NG (RMS SYM	I):	65000A	PER GE DWG <u>75C143992 PV44</u>
DEV.MIN.INT.R	ATING (RMS SY	M):	65000A	PER PWR CO SPEC. <u>75C143991 SH. 42</u>





Drawing For Reference Only

PROJECT NAME:
NYPA EVI SWBD


CUSTOMER:
ABB INC, CARY

DWG TITLE:
Front View/
Bussing


CREATED BY: Sherif, Tarek
CHECKED BY: Spectra Series
APPROVED BY: DATE: 6/8/2019 2:09:21 AM
REVISION NO.:



ACCESS TO	: Front Only	PHASE:	3P4W	CONSOLIDATED EDISON NY, Spec, 377
CLASS:	2	AMPERE	: 1200A	CODE C3
LABEL:	U/L SE	BUS MTL		C/T TYPE Window
VOLTAGE:	480/277V	PLATE:	Tin Plate	P/T TYPE
STYLE:			Fully Rated	
BUS BRACIN	NG (RMS SYM):	65000A	PER GE DWG <u>75C143992 PV44</u>
DEV.MIN.INT.RATING (RMS SYM):			65000A	PER PWR CO SPEC. <u>75C143991 SH. 42</u>




Top Conduit Area



Front Plan View

Bottom Conduit Area



Front Plan View

PROJECT NAME :	DWG TITLE:	CREATED BY: Sherif, Ta	ek PRODUCT NAME:
NYPA EVI SWBD	Conduit View	CHECKED BY:	Spectra Series
CUSTOMER:		APPROVED BY:	'
ABB INC, CARY		DATE: 6/8/2019 2:09:21 A	M Switchboard
•		REVISION NO.:	



	DRAWING NO:	
١	ITEM NO:	1
/	MARKS:	
	QUOTE NO:	U77-00007435
าร	SHEET:	3 of 3

Fast Charging Stations (For Reference Only)

Manufacturers:

- ABB Terra High Power GEN III
- BTC Power Modular HPC System
- Signet EV DP 350K & HPC 175K
- Tritium Veefil PK HPC



PRODUCT LEAFLET

Electric Vehicle Infrastructure

Terra High Power - GEN III



ABB's Terra HP generation III charge post is a 175 to 350 kW high power charger ideally suited for highway corridor and EV fleet applications. With ABB Dynamic DC power sharing technology, power cabinets can be connected to charge one vehicle at up to 350 kW and 500 A or two vehicles simultaneously at up to 175 kW and 375 A. This architecture enables higher utilization of charging assets.



Premium user experience

Easy to use

Terra HP generation III charge post offers a premium charging experience with high output power at low noise levels, a long charge cable with cable retraction system, small footprint of the charge post, and several authentication, payment and customization options.



Brand experience

Customizable branding

Make the charger a real part of your brand image for an optimum user experience. Customize the charger by applying wrapping, selecting a matching color for the LED strips, and customizing the user interface to match brand identity.



Profitable operation

Built for business

Terra HP fully supports commercial operation with Dynamic DC power sharing to optimize use of charging assets, site energy management solutions to enable future growth while optimizing grid connection costs, and remote software updates enabling a future proof system supporting today's and tomorrow's EVs.

Key features

- · Long cables with cable retraction system.
- 500 A charging at low noise levels.
- Elegent charge post in small foot-print with integrated cooling system.
- High level of user safety backed by third party testing.
- Integrated RGB LED strips with customizable color.

Optional features

- Dynamic DC power sharing.
- Customizable user interface.
- Integrated payment terminal.

 $500\,A$ continuous up to $35^{\circ}C$ with noise level of \leq 60 dB(A) at 1 m

500 A CCS (liquid cooled) 200 A CHAdeMO

150 - 920 V DC

68 dB(A) at 1 m

15" high brightness

5.3 m / 17 ft with retraction system

Technical specifications

Charging performance

Charge post

Charge cable

Touch screen

Environment

Storage

Altitude


Operating temperature


DC output current


DC output voltage

Maximum noise level

Dynamic DC power sharing illustrated







Simultaneous charging at up to 175 kW and 375 A at both charge posts.

Why charging operators prefer ABB

- ABB Ability[™] Connected Services:
- Charger Connect: Easily connect chargers to OCPP back offices, over-the-air software updates.
- Charger Care: Remote diagnostics and resolution, service case management, notifications, data export.
- ABB's decade of EV charging experience and close cooperation with EV OEMs, networks and fleets.
- High volume production with a globally distributed manufacturing base.
- Industry leading uptime with a global and local service presence.

	3 - 3
RFID	ISO/IEC 14443A/B, ISO/IEC 15393, FeliCa™1, NFC, Mifare, Calypso
Network connections	4G, Ethernet
Dimensions (H x W x D)	2458 x 590 x 425 mm / 96.8 x 23.2 x 16.7 in
Weight	250 kg / 551 lbs
Connector types	CCS1 / CCS2 / CHAdeMO
Power cabinet	
Output power	175 kW up to 40°C
Output power derating	5% per 5 additional degrees
Output current	1 cabinet: 375 A 2 cabinets: 500 A
AC connection	L1, L2, L3, GND (no neutral)
CE version	400 V AC ± 10%, 50 Hz (option: 60 Hz) 277 A, 192 kVA nominal Recommended breaker: 315 A
UL version	480Y/277 V AC +/-10%, 60 Hz 231 A, 192 kVA nominal Recommended breaker: 300 A
CSA version	600 V AC ± 10%, 60 Hz 185 A, 192 kVA noninal Recommended breaker: 250 A
Short circuit rating	CE: 25 kAIC UL/CSA: 65 kAIC
Overvoltage	CAT III
Efficiency	≥ 94% at full load
Power factor	≥ 0.97
THDi	≤ 8%
EMC emission (conducted)	Standard: Class A (industrial) Optional: Class B (residential) with external filter
Noise level	≤67 dB(A) at 1 m
Dimensions (H x W x D)	2030 x 1170 x 770 mm / 79.9 x 46.1 x 30.3 in
Weight	1340 kg / 2954 lbs
System	
Compliance	CE, cTUVus for UL and Canada

For more information



abb.com/ev-charging

E-mail: info.evi@nl.abb.com

IP54, NEMA 3R outdoor use

-35 °C to +55 °C (derating applies) +5 to +40 °C with RH 5 to 85%

IK10 (screen: IK08)

2000 m / 6560 ft

Modular HPC System: 100, 150, 200 KW

PARAMETERS	POWER ENGINE CABINET MODEL			
PARAIVIETERS	HPCT-100	HPCT-150	HPCT-200	
Power Rating	100 kW	150 kW	200 kW	
Number of Power Engines	2	3	4	
Input Power	480VAC-3P@132A	480VAC-3P@198A	480VAC-3P@264A	
Input Power AC Current (FLA)	132 A	198 A	264 A	
Power Stage Efficiency Rating	> 92% (Full Load)			
Max. Out DC Current up to 920 VDC	108 A	162 A	216 A	
Max. Out DC Current up to 500 VDC	250 A	375 A	500 A	
Max. Output DC Voltage	50 - 950 VDC			
Max # of Dispensers	2	2	2	
Dimension & Weight	42"W x 35"D x 82"H, 1400/1650/1900 lbs			

PARAMETERS	DISPENSER MODEL					
PARAIVIETERS	HPCD-125		HPCD-200		HPCD-350	
Rated Output Current	125 A	125 A	200 A	200 A	350 A	200 A
Connectors	SAE CCS1	CHAdeMO	SAE CCS1	CHAdeMO	SAE CCS1 (Liquid Cooled)	CHAdeMO
Max DC Voltage (VDC)	500 V	500 V	950 V	500 V	950 V	500 V
Network	OCPP 1.5/1.6, BTCP Network					
Output Power	50 kW max 200		200 kV	N max	350 kV	V max
Input Power (Auxiliary)	120 VAC					
Input Current (Auxiliary)	20 A					
Breaker Size	30 A					
Dimension & Weight	22"W x 15"D x 97"H, 600 lbs					

ENVIRONMENTAL AND COMPLIANCE (SYSTEM)		
Ambient Condition	-30 °C to +50 °C, 95% Humidity, 6000 ft Altitude. NEMA 3R	
Safety Compliance	ETL Listed for USA and Canada: Complies with UL 2202, UL 2231 UL50E, NEC	
	Article 625, CSA STD C22.2 No. 107.1 FCC Part 15 Class A	

▶ STANDARD

- > Dynamic Power Allocation in 50kW increments
- > System available in one or two dispenser configuration
- Payment types: CC, RFID (OCPP Network Enabled)
- > 15" Outdoor Color Display
- > Connector Configuration:
 - SAE J1772 Combo CCS1 and CHAdeMO

▶ OPTIONAL

- > ISO 15118:2014
- Customizable Backlit Acrylic Topper
- Apple & Android Pay (based on network provider)
- > Connector Configurations:
 - Dual SAE J1772 Combo CCS1
 - Single CHAdeMO
 - Single SAE J1772 Combo CCS1

Drawing For Reference Only



1719 S Grand Ave, Santa Ana CA, 92705



Electric Vehicle Charging Station

Installation Manual


DP350K-DCM DP350K-CC HPC-175K

Revision History

Revised Version	Revised Date	Revised Details	
1.0	01.13.2020	Inital	

Models






Dispenser

HDP 350K - NCM2

Combo + Combo


Dispenser
HDP 350K - NCC
Combo + CHadeMo



Power cabinet HPC 175K

Installation Manual Installation Manual

Dispenser - 2/2



Specifications

Specifications

The following table lists the specifications for the EV Charging Station.

Power Cabinet

	ltem	HPC 175K (1 set) (150 kW power config)	HPC 175K (2 sets) (350W power config)	
	Voltage	3-phase, 480y/277 (4-wire)		
	Voltage Range	10 %		
AC Input	Frequency	50/60 Hz		
	Current (peak)	227 A		
	Power	173 kW	346 kW	
DC 0 1 1	Max. Voltage	DC 200 – 92	0 V	
DC Output	Max. Power	161 kW	322 kW	
Power	Factor	More than 0	.99	
Efficier	ncy (full load)	94.5 %		
	Mfr recommended overcurrent protection 300 A			
Total Harmonic Distortion		3.9		
Operating Temperature		-30 °C – +50 °C (-22 °F – +122 °F)		
Humidity		95 %		
IP Rating		Nema, Type 3R, Rain Proof		
IK Rating IK08		IK08		
Short Circuit Rating		65 kA (part number starting with QB)		
Altitude		3,000 m		
Power Cabinet Weight		882 lb (400kg)	1,764 lb (800kg)	
	Power Cabinet Dimensions 41.97 x 29.45 x 83.3 (W x D x H) (1,066 x 748 x 2,118		83.94 x 22.05 x 83.39 in (2,132x 748 x 2,118 mm)	

Installation Manual


Dispenser


ltem		Descri	ption	
		Model: HDP350K-NCM2 (CCS1 + CCS1 config)	Model: HDP350K-NCC (CCS1 + CHAdeMO config)	
	Max. Voltage		920 V	
DC Output	Max. Current	460V/500A, 920V/350A		
	Max. Power	350KW	350 kW for CCS1 100 kW for CHAdeMO	
Operating Ter	mperature	-30 °C − +50 °C	C (-22 °F – +122 °F)	
• Reverse polarity protection • Short circuit protection • Over temperature protection • Over-voltage / Under-voltage p		Short circuit protectionOver temperature protectionOver-voltage / Under-voltage protection	ection	
Display (LCD)		15 in touch screen		
IP Rating		NEMA, Type 3R, Rain Proof		
IK Rating		IK08		
Altitude		3000 m		
Dispenser Weight		551 lb		
Dispenser Dimensions 28.03 x 22.05 x 99.24 in (W x D x H) (712 x 560 x 2,521 mm)				
Payment Debit and credit cards, mobile, NFC payments, swipe, contact or contactless				
Communication		OCPP 1.6 JSON over Websockets		


Dimensions

The following diagrams show the dimensions of the Power Cabinet and Dispenser.

Power cabinet








Drawing For Reference Only

http://www.signetev.com/

Installation Manual Installation Manual

Dispenser




Drawing For Reference Only

Installation Pad Dimensions

The following diagrams show the dimensions of the installation pads for the Power Cabinet and Dispenser.

Power cabinet - 175 kW





VeefilPK

High Power Charging System



A scalable, flexible high power charging (HPC) system for commercial operators.

- + High energy efficiency
- + Dramatically smaller footprint
- + Effortless charging experience
- + Minimal maintenance
- + Maximum uptime
- **+** IP65

Dependable · Scalable · Profitable

NOW • IN THE FUTURE • ALWAYS

350kW

USER UNIT

CONNECTOR	CCS Type 1, CCS Type 2 & CHAdeMO
	Single or dual cable option
OUTPUT POWER	Up to 350kW
OUTPUT VOLTAGE	Up to 920Vdc
OUTPUT CURRENT	CCS: Up to 500A
	CHAdeMO: Up to 200A
IP RATING	IP65
EFFICIENCY	98.5%
OPERATING TEMPERATURE	-35°C to 50°C
CREDIT CARD READER	Optional
DIMENSIONS	1998(H) x 980(W) x 525(D) mm
WEIGHT	260Kg
RFID READER	MIFARE ISO/IEC14443A/B, ISO/IEC15693,
	ISO/IEC18000-3, FeliCa, NFC, EMV 2.0
CABLE LENGTH	4.3m
THD	<5%
IK RATING	IK 10

POWER UNIT

INPUT	2 X 480V 3ph 50Hz
OUTPUT	2 X 950Vdc 350kW
IP RATING	IP54
EFFICIENCY	>98%
POWER FACTOR	0.99
OPERATING TEMPERATURE	-35°C to 50°C
NETWORK CONNECTION	Ethernet to User Unit and Control Unit Site Power Control
WEIGHT	700Kg
DIMENSIONS	2350(H) x 603(W) x 1230(D) mm
IK RATING	IK 10

CONTROL UNIT

WIRELESS CONNECTIVITY	3G/4G cellular communications with
	failover redundancy
WIRED CONNECTIVITY	Ethernet capability
POWER SUPPLY	Battery-backed UPS functionality for reliable
	telemetry at all times
SOFTWARE SUPPORT	OCPP1.6J support for management and billing
IT SECURITY	SSH with EC keys & unique password for
	manufacturer diagnostics
POWER SHARING	Configurable site-level power demand management
POWER CONTROL	Power sharing algorithms can be easily added and
	modified to allow for various sharing configurations
CONTROL PLATFORM	Gives owner/operators vital real-time information
	on the status and performance of the charging station
WEIGHT	220Kg
DIMENSIONS	2350(H) x 603(W) x 1230(D) mm
IK RATING	IK 10



With the flexibility of different colours and branding design, the Veefil-PK is easily adapted to suit your corporate image.

ABOUT TRITIUM

Tritium is committed to your electric vehicle charging success. Tritium offers a flexible, responsive and dedicated approach to electric vehicle charging networks around the world. Established in 2001, and backed by government and private investors, Tritium has a growing global presence with installations in over 29 countries and offices in three continents.









Parking Lot Security References

<u>Security Requirements: IP Cameras with the following minimum specifications:</u>

- 10 MP, 1/3 in progressive scan
- Lens 3.8x(3.0mm to 9.00mm) variable focal length
- 350° Horizontal angle adjustment, 80° tilt
- 1 lux, f2.0 min illumination
- Video motion detection
- Active tampering alarm
- Color to Black/White switching (Day/night) automatic swithcin IR cut filter mechanism
- Compression and frame rate H.264, MJPEG and MPEG-4 32fps each simultaneously

