

ITEM 202.28xxxx10 M - DEBRIS REMOVAL FOR SPECIAL AREAS

DESCRIPTION:

This work shall consist of pick up and disposal of debris in and along streams and water bodies, in recharge basins, adjacent to the highways and parkways, and other areas, at locations as indicated in the contract documents and as directed by the Engineer.

For the purpose of this specification debris shall be defined as any discarded material that is visible on the ground including but not limited to cans, bottles, coffee cups, paper, plastic, wrack line debris, food wrappings. Debris shall also include other dumped materials such as building materials and landscape debris, as determined by the Engineer. Materials such as appliances, vehicle tires and other materials identified by the Engineer are not part of this item. All debris identified on the plans for removal under this item is considered to be uncontaminated. If any material is encountered that cannot be classified as uncontaminated, it shall be reported to the Engineer.

MATERIALS:

None specified.

CONSTRUCTION DETAILS:

Equipment for debris removal may be selected by the Contractor, but shall be subject to the approval of the Engineer and shall conform to all applicable local, state and federal laws, regulations and codes. The work required to remove debris from surfaces shall be performed in accordance with these specifications, the contract documents, wetland permits and to the satisfaction of the Engineer. The limits of debris removal shall be as indicated in the contract documents. The Contractor shall notify the Engineer 48 hours in advance of performing any work under this item. The Contractor shall supply all necessary flags, signs, and other devices, equipment and personnel necessary to maintain and protect traffic as indicated in the Contract proposal. Work shall be conducted in such a manner that plants and wetland areas will not be damaged. All disturbed areas shall be restored as per Section 107-08 and approved by the Engineer. All debris removed under this item shall be legally disposed at registered dump sites pursuant to 6NYCRR Part 360 regulations and shall not be stored in the State right-of-way. The Contractor shall provide receipts for disposal to the Engineer within three days of disposal.

METHOD OF MEASUREMENT:

This work will be measured by each location from which debris is removed as shown on the contract plans.

BASIS OF PAYMENT:

The unit price shall include the cost of all labor, materials and equipment necessary to complete the work. No separate payment will be made for maintenance and protection of traffic but this cost is to be included in the price bid for removal of debris.