

ITEM 10202.8001 M - REMOVAL OF TIMBER JACKETS

DESCRIPTION

The work specified herein shall consist of the removal and legal disposal of the existing timber jackets on the existing concrete piles at the locations indicated on the Plans.

MATERIALS

None specified.

CONSTRUCTION DETAILS

Protection of Adjacent Work

The Contractor shall exercise care during the execution of the work to avoid damaging adjacent material that is to remain. All damage caused by the Contractor's operations to adjacent material that is to remain shall be repaired in a manner satisfactory to the Engineer at no additional cost to the State.

The Contractor shall submit resumes of the diving personnel employed for underwater work. All diving personnel shall have had at least three years of diving experience.

Removal of Jackets

All timber jackets shall be removed in their entirety.

Disposal

All timber jackets removed shall become the property of the Contractor and shall be removed by him from the site of the work to a legal disposal site.

All timber jackets shall be disposed of in a manner satisfactory to the Engineer.

If any timber jackets are to be disposed of on private lands, written permission from the owner or owners of such lands shall be submitted to the Engineer prior to starting disposal operations.

METHOD OF MEASUREMENT

This work will be measured as the number of timber jackets removed.

BASIS OF PAYMENT

The unit price bid for each timber jacket removed shall include the cost of all labor, materials and equipment necessary to complete the work.