

ITEM 10202.83 M - REMOVAL OF EXISTING TIMBER DOLPHINS

DESCRIPTION

The work shall consist of the complete removal and disposal of the seven pile cluster timber dolphins located at the east and west ends of the waterway piers as indicated on the Plans.

MATERIALS

None specified.

CONSTRUCTION DETAILS

The Contractor shall remove from the site and dispose of the existing timber dolphin piles at the east and west ends of the waterway piers as shown on the Plans. The existing piles of the dolphins including broken piles shall be completely removed so as not to interfere with the installation of the new timber piles being installed for the new dolphins at the same location or to pose a hazard to navigation.

METHOD OF MEASUREMENT

This work will be measured by the number of timber pile dolphins removed. Each timber pile dolphin consists of seven piles with cable wrapping.

BASIS OF PAYMENT

The unit price bid for each timber pile dolphin removed shall include the cost of furnishing all labor, materials and equipment necessary to complete the work.

DISAPPROVED EIT 10202.83 M