

ITEM 202.9902 11 M - REMOVAL OF STONE, ASPHALT AND CONCRETE

SIDEWALKS AND BIKEWAYS

DESCRIPTION

This work shall consist of removing existing stone, asphalt and concrete sidewalks and bikeways at locations indicated in the Contract Documents and where directed by the Engineer.

MATERIALS

None specified.

CONSTRUCTION DETAILS

This work shall consist of the following:

- A. Removing and disposing of existing stone (various types - granite, slate, bluestone, etc.), asphalt and concrete sidewalks and bikeways to a depth indicated in the Contract Documents and where directed by the Engineer. Care shall be taken not to damage adjacent sidewalk and other appurtenances that are to remain. Sawcutting the existing sidewalk or bikeway at the limits of removal shall be as directed by the Engineer.

Any damage to the sidewalk or bikeway or appurtenances that are to remain caused by the Contractor's operation during the sidewalk removal and disposal operations shall be repaired and/or replaced by the Contractor at no expenses to the State. These repairs and/or replacement shall be as directed by and approved by the Engineer.

- B. Material removed under this item shall be disposed of or recycled by the Contractor.

METHOD OF MEASUREMENT

This work will be measured as the number of square meters of satisfactorily removed stone, asphalt and concrete sidewalk and bikeways, as approved by the Engineer, and as computed from payment lines detailed in Contract Documents and where directed by the Engineer.

BASIS OF PAYMENT

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work. The cost of sawcutting shall be included in the cost of this item. Sidewalk and bikeway removed for replacement of portions damaged by the Contractor's operations shall not be measured for payment. Removal of sand setting bed and/or subbase will be paid for under the Unclassified Excavation item.