

**ITEM 02203.0192 M - UNCLASSIFIED EXCAVATION AND EMBANKMENT OF CONTAMINATED MATERIAL**

**DESCRIPTION**

This work shall consist of the excavation, relocation, grading and compaction of contaminated soils as indicated on the contract plans or as designated by the Engineer.

**MATERIALS**

Contaminated soils excavated within the contract limits. No material testing requirements shall apply.

**CONSTRUCTION DETAILS**

Section 203-3 of the General Specifications shall apply in addition to the following:

- a. The contractor shall excavate, stockpile, relocate to grade and compact the soils identified in the plans or as directed by the Engineer. All work shall be performed in accordance with this specification, details, and/or any special notes.
- b. The contractor shall complete the spreading of the stockpiled material in accordance with specification within 45 calendar days from the time the contaminated soil is excavated.
- c. The contractor shall follow rules and regulations that pertain to the safety of the workers when handling the contaminated soils.

**METHOD OF MEASUREMENT**

Section 203-4.02 of the General specifications shall apply in addition to the following:

- a. The limits for payment are identified in the contract plans for the contaminated soil relocation areas.
- b. The quantity shall be in cubic meters as computed in it's original position from the final payment limits established by the Engineer. No additional measurements or payments will be made for stockpiling or placement of materials in accordance with this specification.

**BASIS OF PAYMENT**

Section 203-5 and 203-5.02 of the General specifications shall apply in addition to the following: the unit price bid shall cover all costs of excavation, stockpiling, placement, de-watering and suitable disposal of excess materials.

January 15, 2003