

**ITEM 17203.1223 M - FURNISHING EQUIPMENT FOR INSTALLING  
PREFABRICATED VERTICAL DRAINS**

**DESCRIPTION**

Furnish equipment at the site of work for installing prefabricated vertical drains where shown on the plans.

**MATERIALS**

Not specified.

**CONSTRUCTION DETAILS**

Provide equipment with a mandrel or sleeve with attached anchor having a minimum cross sectional area of 9,000 square millimeters.

Submit for approval the type of equipment proposed for use to the Engineer 30 days prior to commencing installation. Remove all equipment deemed unsatisfactory by the Engineer from the site and replace it with satisfactory equipment at no additional cost to the State.

**METHOD OF MEASUREMENT**

Payment will be made by lump sum.

**BASIS OF PAYMENT**

Include the cost of all labor, materials and equipment necessary for transporting, erecting, maintaining, making any ordered equipment replacement, dismantling and removing all installation equipment in the lump sum price bid. Payment will be as follows: Seventy-five (75) percent of the amount bid will be paid when the approved equipment for installing prefabricated vertical drains is furnished and the installation has commenced. The remainder will be paid when the work of installing prefabricated vertical drains is completed.