

ITEM 06203.1406 M - BACKING UP OF NEWLY PAVED SHOULDERS

DESCRIPTION

This work shall consist of grading and compacting existing suitable material as determined by the Engineer or furnishing, placing, grading and compacting suitable material adjacent to the newly placed shoulders as necessary to eliminate the drop-off to original ground. This work shall be done at locations and per details shown in the Contract Plans, or A.D.B.E.

MATERIALS

New materials shall meet the requirements of §304, Subbase Course of the Standard Specifications with the following modifications:

1. The soundness requirements of Section 304-2.02 will be waived.
2. The stockpiling requirements of Section 304-2.03 will be waived.
3. The percentage of material passing the NO. 75 μ m Sieve shall be 0 - 15%.

CONSTRUCTION DETAILS

The newly paved shoulder shall be backed up with a wedge section of suitable material as called for in the Contract Plans. The procedure for placing and compacting the material shall be in accordance with the requirements of the Engineer.

METHOD OF MEASUREMENT

The unit of measure for this item shall be the number of linear meters, measured along the edge of shoulder where the shoulder backup material is properly placed, graded and compacted.

BASIS OF PAYMENT

The unit price bid per linear meter shall include the cost of all labor, materials and equipment necessary to satisfactorily complete the work.