

## **ITEM 05203.1407 M - SHOULDER BACKUP FOR NEWLY PLACED SHOULDERS**

### **DESCRIPTION:**

This work shall consist of furnishing, grading and compacting granular material adjacent to the newly placed shoulders as necessary to eliminate the drop-off to original ground. This work shall be done at locations and per details shown in contract plans, or as directed by the Engineer.

### **MATERIALS:**

Granular material shall meet the requirements of Item 203.07 M, Select Granular Fill, of the Standard Specifications with the following modifications:

1. The percentage of material passing the 25 mm sieve shall be 100 percent.
2. The percentage of material passing the 425  $\mu\text{m}$  sieve shall be 5 to 40 percent.

### **CONSTRUCTION DETAILS:**

The newly paved shoulder shall be backed up with a wedge section of approved material as shown in the contract plans, or as directed by the Engineer. The material shall be placed and compacted to the satisfaction of the Engineer.

### **METHOD OF MEASUREMENT:**

The unit of measure for this item will be the number of meters measured along the edge of shoulder where the shoulder backup material is properly placed, graded and compacted.

### **BASIS OF PAYMENT:**

The unit price bid per meter shall include the cost of all labor, material and equipment necessary to satisfactorily complete the work.