

ITEM 08203.1721 M - REMOVE STORE AND/OR DELIVER ROCK CATCHMENT FENCE

DESCRIPTION:

This work shall consist of removing, storing, and/or delivering the existing rock catchment fence as noted in the contract documents.

MATERIALS:

None

CONSTRUCTION DETAILS:

The Contractor shall start the removal of the rock catchment fence no sooner than three weeks before the commencement of the rock blasting operation. After removal of the rock catchment fence, the Contractor may store materials but shall follow all manufacturer recommendations for storage.

The Contractor shall inform a state representative at the location noted in the contract documents a minimum of two days before the delivery of the rock catchment fence.

During the removal, storage, and/or delivery, the Contractor shall take appropriate precautions to insure that all parts of the rock catchment fence are not damaged and can be reassembled to perform as specified by the manufacturer's information.

METHOD OF MEASUREMENT:

This work will be measured as the number of linear meters of rock catchment fence removed, stored, and/or delivered as noted in the contract documents.

BASIS OF PAYMENT:

The unit price bid per linear meter for this item shall include the cost of furnishing all labor, equipment and incidentals required to do the work.