

ITEM 63203.30XX M - EXCAVATION AND DISPOSAL OF ROCK, EMERGENCY STANDBY

DESCRIPTION:

This work shall consist of excavation and disposal of rock required pursuant to the implementation of an Emergency Stand-by Contract. This item of work will be used only in the instance where work of an emergency nature is needed and will include only that portion of the excavation deemed by the Geotechnical Engineering Bureau to be firm rock, in its natural position, that in the opinion of the State, can not be practically excavated by mechanical methods, and will require pre-splitting under the provisions of Section 203-3.05.

MATERIALS:

Not applicable.

CONSTRUCTION DETAILS:

Sections 203-3.01 and 203-3.05 shall apply.

METHOD OF MEASUREMENT:

The provisions of Section 203-4.01 and 203-4.03 shall apply. In addition, only that portion of excavation consisting of rock shall be included in the computation for this work. Excavation of soil, boulders, previously fallen ledge, boulders or ledge that have been pulled off a slope, loose rock, overburden, concrete, hardpan, or rock that could be mechanically excavated (ripped) in the opinion of the State (as determined by the Geotechnical Engineering Bureau) shall not be included in the computation of this work. No portion of a slope excavated to a slope flatter than one vertical on one horizontal shall be included in this work. Work done pursuant to Section 206 shall not be included in the computation of this work.

The State may, at its option, compute the quantity to be paid by weighing the rock (as defined in the above paragraph) and converting the weight to equivalent volume in cubic meters based on the specific gravity of the rock excavated. In such case suitable truck scales shall be provided by the contractor.

BASIS OF PAYMENT:

All provisions of Section 203-5.01 shall apply. In addition, the unit price bid shall include the cost of furnishing and maintaining truck scales.

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
63203.3001M	Excavation and Disposal of Rock, Emergency Standby Contract Work, Quantity Range 1 (0.0 to 99.9)	m ³
63203.3002M	Excavation and Disposal of Rock, Emergency Standby Contract Work, Quantity Range 2 (100.0 to 499.9)	m ³
63203.3003M	Excavation and Disposal of Rock, Emergency Standby Contract Work, Quantity Range 3 (500.0 to 1000.0)	m ³