ITEM 03203.9943 M - SPECIALIZED ITEM FOR HANDLING OF CONTAMINATED MEDIA

DESCRIPTION

The Contractor shall perform all site preparation; poly sheeting placement; movement, staging and loading of contaminated media (soil, water, and debris); construction, operation and removal of decontamination pad; decontamination of personnel and equipment; site restoration; safe operating procedures in accordance with 29 CFR Part 1910.120; and all requirements for conducting excavation and work in an industrial contamination site as delineated in the General Note under Industrial Contaminated Soil and Water or in the NYSEG work plan.

MATERIALS

Furnish all materials and equipment to conduct the project excavation and construction requirements within the contaminated area in accordance with the NYSEG work plan.

CONSTRUCTION DETAILS

The contractor shall perform all the requirements and additional routine excavation for working in a contaminated area in accordance with 29 CFR 1910.120 and the NYSEG work plan. Disposal of contaminated waste soils and water will be handled by NYSEG and will not be the Contractor's responsibility . The contractor shall perform all site preparation; poly sheeting placement; movement, staging and loading of contaminated media (soil, water, and debris); construction, operation and removal of decontamination pad; decontamination of personnel and equipment; site restoration; safe operating procedures in accordance with 29 CFR Part 1910.120; and all requirements for conducting excavation and work in an industrial contamination site as delineated in the General Note under Industrial Contaminated Soil and Water or in the NYSEG work plan. Employees conducting work in contaminated areas shall be trained per 29 CFR 1910.120.

The contractor shall 30 days before construction of the project submit a materials handling plan. This plan at a minimum shall conform to the NYSEG work plan and provide all the items identified in the description section. The contractor shall be responsible for loading waste media into the proper waste conveyance vehicle supplied by NYSEG.

BASIS FOR ACCEPTANCE

Completion of all activities in the contaminated areas in accordance with the NYSEG Work Plan and the additional tasks identified in the Description.

METHOD OF MEASUREMENT All work necessary to complete the assigned tasks.

BASIS OF PAYMENT The unit price shall be a lump sum based on the work to be performed.

Payment will be made under:

ITEM NO.		
03203.9932 M	SPECIALIZED ITEM FOR HANDLING OF CONTAMINATED MEDIA	Lump Sum