

**ITEM 206.03 11 - ROCK EXCAVATION FOR CONDUIT AND JUNCTION BOX
PLACEMENT, NON-EXPLOSIVE**

DESCRIPTION

Under this item, the contractor shall remove rock along the proposed conduit line or at new junction box location in accordance with the contract documents or where ordered by the Engineer, using a non-explosive method acceptable to the Engineer.

MATERIALS

Mechanical or pneumatic breakers or rotary pavement cutter will be allowed. If a chemical expanding agent is selected, it should be used in accordance with the manufacturer's directions, and in a manner acceptable to the Engineer.

CONSTRUCTION DETAILS

Care shall be taken so as not to damage property during the rock excavation operation. The Contractor shall be responsible for the repairs of all damage resulting from the excavation operations, as ordered by the Engineer at no cost to the State. All work shall be conducted in a safe and professional manner.

METHOD OF MEASUREMENT

This work will be measured as the number of cubic meters of rock excavated, computed from payment lines shown on the plans, or where changes have been ordered from payment lines established by the Engineer.

BASIS OF PAYMENT

The unit price bid per cubic meter shall include the cost of furnishing all labor, materials and equipment necessary to satisfactorily complete the work. It shall also include the cost of furnishing all protective devices, and all safety-related devices necessary to complete the work, including any repairs required due to the Contractor's operation.