

## **ITEM 06303.87 M - SHOULDER BACKUP WITH STABILIZED MATERIAL**

### **DESCRIPTION**

This work shall consist of furnishing, placing, grading, and compacting suitable material adjacent to newly placed shoulders to eliminate the drop-off to original ground. This material shall be placed at the locations and according to the details shown on the contract plans.

### **MATERIALS**

Shoulder backup material shall meet the requirements of Item 302.01.

### **CONSTRUCTION DETAILS**

The Contractor shall place shoulder backup material as shown on the typical sections and details in the contract documents. This material shall be graded and compacted to the satisfaction of the Engineer.

### **METHOD OF MEASUREMENT**

This work shall be measured as the number of linear meters of shoulder where backup material is properly placed, graded, and compacted.

### **BASIS OF PAYMENT**

The unit price bid for this item shall include all costs of furnishing, placing, grading, and compacting shoulder backup material.

DISAPPROVED BY EIT 11-020