

ITEM 402.00004391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 1
ITEM 402.00005391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 2

DESCRIPTION

Measure the ride quality of the finished riding surface using a verified and properly calibrated inertial profiler. Report test results to the Engineer as an average International Roughness Index (IRI) for the right wheelpath of each pavement-ride-quality (PRQ) lot. The pavement and all other quality adjustments are constructed, measured and paid for under their appropriate items.

For the purposes of this specification, the following terms are defined below.

Calibration. All procedures, contained in Materials Method 24.1, followed to ensure that each individual data collection device is operating properly.

International Roughness Index (IRI). An index computed from a longitudinal profile measurement reported in m/km. For this specification IRI is computed according to the quarter-car model. IRI computed according to the quarter-car indicates the amount of suspension travel that one wheel of a standard vehicle would experience when traveling over a longitudinal profile.

Measurement. A single determination of IRI along the reference line for the entire length of a single PRQ lot in the direction of traffic.

Pavement Ride Quality (PRQ) Lot. A PRQ lot is a continuous 200 m section of pavement one lane wide, in areas shown in the contract documents as requiring pavement ride quality testing. Ride Quality testing is performed for each PRQ lot. Payment adjustments are made separately for each PRQ lot.

Quarter-car Model. A mathematical model of one wheel (one quarter) of a car of a standard weight with a standard tire, standard spring rate and standard damping. The standard car is also known as the "golden car" and was established in NCHRP Report 228.

Reference line. The imaginary line the noncontact height sensor traces along the pavement surface. The intended reference line for all QC and QA tests is located 0.9 m to the left of the right edge of the PRQ lot (right wheelpath). The closer all tests are taken to the same reference line, the less variability will occur between the results.

Test. The average of three consecutive measurements taken on the same day in the same PRQ lot by the same inertial profiler and operator.

Verification. All procedures, contained in Materials Method 24.1, followed to ensure the test results produced by a profiler are within an acceptable variation of the true profile.

MATERIALS None Specified

CONSTRUCTION DETAILS

ITEM 402.00004391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 1
ITEM 402.00005391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 2

Test and report the ride quality of all new flexible pavement and HMA overlays of pavement and bridge decks except: shoulders, gore areas, ramps shorter than 400 m, turn-outs, turn-arounds, driveways, parking areas and other similar miscellaneous paving.

- A. Inertial Profiler Requirements.** A self-powered test vehicle conforming to ASTM E950 Class I and AASHTO PP 50-02 containing automated test initiation and data recording systems capable of providing the following information to the on-board display, onboard data storage device, and on-board printer.
- The date, time, contract number, route, location, test direction, lane and operator for each test.
 - The equipment parameters related to calibration.
 - A general profile, using a scale of 1:300 horizontal and 1:1 vertical.
 - The average IRI and range for the specified wheelpath for each PRQ lot.

Alternative equipment types may be used as approved by the Director, Materials Bureau. Submit requests to use alternative equipment to the Director, Materials Bureau, at least 14 days prior to the start of QC testing. Alternative equipment will be approved provided it meets the requirements for inertial profilers.

B. Equipment Verification, Calibration and Daily Control Section Testing.

- 1. Verification.** Prior to using an inertial profiler on a Department project, the profiler must be verified according to Materials Method 24.1.
- 2. Calibration.** Calibrate the inertial profiler according to frequency and procedures given in Materials Method 24.1.
- 3. Daily Control Section Testing.** Create a control section at or near the project site according to the procedures of Materials Method 24.1. Each day of quality control testing, perform one measurement on the control section. Record the results and track the performance of the inertial profiler according to the procedures of Materials Method 24.1.

C. Quality Control (QC) Measurements.

- 1. Layout PRQ Lots.** Divide the pavement areas designated in the contract documents as requiring pavement ride quality testing into PRQ lots according to the following instructions.
 - Divide surface course pavement constructed each day into 200 m sections of pavement one lane wide.
 - Each PRQ lot must be continuous. PRQ lots may not straddle areas not designated for ride quality testing.
 - Include pavement sections shorter than 100 m located between a PRQ lot and an area not designated for ride quality testing or the end of the project in the adjacent PRQ lot.
 - Pavement sections at least 100 m long, but less than 200 m, located between a PRQ lot and an area not designated for ride quality testing or the end of the project will be separate PRQ lots.
 - PRQ lots may include pavement placed on more than one day.

ITEM 402.00004391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 1
ITEM 402.00005391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 2

- Remaining areas at the end of each day's paving which are less than 200 m long will be tested with the adjacent pavement after it is constructed.

2. Perform QC Testing. Perform one test in every PRQ lot according to Test Method NY 402-01F. Perform QC testing after the final surface course has been paved and compacted.

If any pavement repair is made in a PRQ lot under the provisions of §105-04 Conformity with Plans and Specifications or under the provisions for corrective action in this specification, repeat the QC testing for that PRQ lot. If repairs are made in the left wheelpath and not in the right wheelpath, establish the reference line and perform the repeat tests in the left wheelpath. The final tests will be used for payment.

3. Report Results. Provide the following information to the Engineer by the end of the next work day, as per §101-02.

a. Daily IRI Testing Summary Report. Provide a daily IRI testing summary report, consisting of a header and results table, to the Engineer as a printout and a computer file. The computer file may be in spreadsheet or ASCII format.

a1. Header. Include the following information in the report header.

- Contract D number
- Date
- Filter Settings

a2. Results Table. Provide a table consisting of 9 columns labeled as shown below and one row for each PRQ lot tested during that day. Report all results in units of m/km calculated to the nearest 0.01 m/km.

| PRQ lot # | Direction | Lane/ Ramp | Begin Station | End Station | Measurement 1 | Measurement 2 | Measurement 3 | Test |
|-----------|-----------|---------------|------------------|----------------|---------------|---------------|---------------|------|
|-----------|-----------|---------------|------------------|----------------|---------------|---------------|---------------|------|

b. Profile Data. Provide a copy of each profile in the electronic format specified in Test Method NY 402-01F. Name each file according to the following format.

"XXXXXXX_YYY_Z.ERD"

XXXXXXX - Reserve first six characters for the numerical portion of the contract number.

YYY - Separated from the first six characters by an underscore. Reserve the next three characters for the first lot number represented by the file.

Z - Separated from the previous three characters by an underscore. Reserve the last character for the number of the measurement (1, 2 or 3) represented by the file.

.ERD - Denotes the file as being in the proper format for evaluation.

E. Corrective Action.

ITEM 402.00004391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 1
ITEM 402.00005391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 2

Repair all PRQ lots identified by the Engineer as needing repair. Repair procedures are subject to the Engineer's Approval. Present the proposed repair procedures to the Engineer at least 48 hours before beginning the repair work. Pavement thickness, location of repair and level of ride quality and effectiveness of a proposed procedure will be primary considerations in determining the proposed procedure's acceptability.

METHOD OF MEASUREMENT

Quality payment adjustments are measured in Quality Units.

- Determined Quality Units for each PRQ lot by using Table 1.
- For PRQ lots of a length different from 200 m, adjust the number of Quality Units according to Equation 1.
- Determine the total number of Quality Units for each day's production by summing the Quality Units from all PRQ lots paved on that day.

| Table 1 Determination of Quality Units | | | | |
|---|---------------|-----------------------|--|-------------------------------------|
| LEVEL 1 | | LEVEL 2 | | |
| PRQ lot IRI (m/km) | Quality Units | PRQ lot IRI (m/km) | Quality Units for Two Courses + (2) | Quality Units for Single Course (2) |
| < 0.60 | 10 | < 0.75 | 10 | 5 |
| 0.61 – 0.85 | 5 | 0.76 – 1.00 | 5 | 2.5 |
| 0.86 - 1.10 | 0 | 1.01 - 1.25 | 0 | 0 |
| 1.11 - 1.30 | -5 | 1.26 - 1.45 | -5 | -2.5 |
| 1.31 - 1.50 | -10 | 1.46 - 1.65 | -10 | -5 |
| > 1.50 ⁽¹⁾ | -20 | > 1.65 ⁽¹⁾ | -20 | -10 |

(1) The Department will evaluate the lot to determine if it will remain in place. The level of ride quality, location, traffic volume and speed limit will be primary considerations in determining if the pavement will remain in place. If the pavement cannot remain in place, repair it according to the procedures under Corrective Action in this specification. If the pavement can remain in place the Raw Quality Units will be calculated according to Table 1.

(2) "Two Courses +" refers to areas at which the Contractor paved two or more paving courses, excluding truing and leveling. "Single Course" refers to areas at which the Contractor paved only a single course, excluding truing and leveling. A project may contain both types of areas.

Equation 1 Quality Units = Quality Units from Table 1 x $\left(\frac{\text{length of PRQ lot (m)}}{200 \text{ m}} \right)$

ITEM 402.00004391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 1
ITEM 402.00005391 PAVEMENT RIDE QUALITY ADJUSTMENT LEVEL 2

BASIS OF PAYMENT

Payment of Quality Units will be made based on the Index Price listed in the contract documents. The index price shown in the itemized proposal for each Quality Unit is considered the price bid. The unit (index) price is NOT to be altered in any manner by the bidder. Should the bidder alter the amount shown, the altered figure will be disregarded and the original price will be used to determine the total amount bid for the Contract.

Include the cost for all equipment and labor required to comply with this specification in the unit bid price for the appropriate surface course HMA Item.

Payment will be made under:

| Item No. | Item | Pay Unit |
|-----------------|--|-----------------|
| 402.00004391 | Pavement Ride Quality Adjustment Level 1 | Quality Units |
| 402.00005391 | Pavement Ride Quality Adjustment Level 2 | Quality Units |

DISAPPROVED BY EI 08-044