

## **ITEM 11551.1080 M - UNDERWATER CUT OFF OF PILES**

### **DESCRIPTION**

Under this item the Contractor shall cut off piles below water flush to the existing mudline. This item applies to existing pile stubs that are too close to the mudline to allow removal of the piles in their entirety, and all piles that have been snapped or have otherwise been broken in the course of attempting to remove them in their entirety.

### **MATERIALS**

Not specified.

### **CONSTRUCTION DETAILS**

Not specified.

### **METHOD OF MEASUREMENT**

The quantity will be the total number of piles cut off at the mudline. If in the opinion of the Engineer, certain piles were snapped or broken off above the mudline as a result of the Contractor's failure to follow approved removal procedures, then those piles will not be included in the payment quantity, i.e., said piles shall be cut off at the Contractor's expense.

### **BASIS OF PAYMENT**

The Unit Price Per Pile Cut Off shall include the cost of furnishing all labor and equipment necessary to cut off and dispose of the pile remnants.