

ITEM 10551.91 M - REMOVAL OF CONCRETE PILES

DESCRIPTION

This work shall consist of the removal and disposal of reinforced concrete piles including pile Jacketing as shown on the Contract Plans, or as directed by the Engineer. Piles shall be removed in their entirety unless ordered by the Engineer.

MATERIALS

(Not specified)

CONSTRUCTION DETAILS

The Contractor is required to extract the piles in their entirety. If the Contractor encounters extreme difficulties to extract the piles, the EIC may permit the Contractor to cut the piles a minimum of one meter below the mud line in an approved manner.

Work shall also include the legal disposal of piles after removal.

Unless specified otherwise on the Contract Plans, construction details shall meet the requirements of subsection 202-3 of the 1995 Standard Specifications as revised by any Addenda.

METHOD OF MEASUREMENT

The removal of concrete piles will be measured as the number of linear meter of piles actually removed. If piles are partially removed as ordered by the Engineer, only the length removed shall be measured for payment.

BASIS OF PAYMENT

The unit price bid per meter for removal of concrete piles shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work.