

ITEM 63552.07XX M - COFFERDAMS (WATER DISCHARGE CONTROL), EMERGENCY STANDBY CONTRACT WORK

All the provisions for item 552.07M shall apply except that the cofferdam may be constructed of earth, earth-filled bags or other materials as approved by the Engineer regardless of need for water discharge control and the method of measurement will be the number of linear meters measured along the circumference of the cofferdam.

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
63552.0701M	Cofferdams (Water Discharge Control), Emergency Standby Contract Work, Quantity Range 1 (1 to 10)	m
63552.0702M	Cofferdams (Water Discharge Control), Emergency Standby Contract Work, Quantity Range 2 (11 to 30)	m