

ITEM 552.15 10 M - INSTALL INTERIM STEEL SHEETING PROVIDED BY L.I.R.R.

DESCRIPTION

This work shall consist of installing interim steel sheeting furnished by the L.I.R.R. at the locations around the bridge substructures and in accordance with the Contract plans. The Contractor shall coordinate this sheeting with sheeting that L.I.R.R. has installed in the vicinity of the bridge substructures. The Contractor will be required to maintain the sheeting while it is serving its function, including the sheeting installed by the L.I.R.R. The interim sheeting will be cut off and removed only to the elevation shown on the plans. The remaining material shall be left in place.

MATERIALS

Provisions of §552-2.03B Interim Steel Sheeting of the Standard Specifications with the following exceptions:

The interim steel sheeting will be provided and delivered to the site by the L.I.R.R. The Contractor shall coordinate with the L.I.R.R. on a location for the material to be delivered to.

CONSTRUCTION DETAILS

The Contractor shall dispose of sheeting that has been cut off. The provisions of §552-3.01 shall apply.

METHOD OF MEASUREMENT

The provisions of §552-4.01 shall apply.

BASIS OF PAYMENT

The provisions of §552-5.03 shall apply.