

**ITEM 63553.03XX M - TEMPORARY WATERWAY DIVERSION, EMERGENCY STANDBY  
CONTRACT WORK**

All the provisions of Section 553, Cofferdams and Waterway Diversion Structures shall apply except:

Method of Measurement will be made based on the diameter of the existing structure that water is being diverted from.

Payment will be made under:

<b><u>ITEM NO:</u></b>	<b><u>ITEM DESCRIPTION</u></b>	<b><u>PAY UNIT</u></b>
63553.0301M	Temporary Water Diversion, Emergency Standby Contract Work, Quantity Range 1 (600 mm Diameter and Smaller)	Each
63553.0302M	Temporary Water Diversion, Emergency Standby Contract Work, Quantity Range 2 (Over 600 mm Diameter to 1200 mm Diameter.)	Each
63553.0303M	Temporary Water Diversion, Emergency Standby Contract Work, Quantity Range 3 (Over 1200 mm Diameter)	Each