

ITEM 553.0404 09 - REMOVAL OF EXISTING TEMPORARY CAUSEWAYS

DESCRIPTION

The Contractor shall remove the existing Chenango River causeway, left in place at the completion of the Phase 1 or as modified during Phase 2 construction. This work shall consist of excavating and disposing of temporary causeways and restoring the channel bottom at the locations and to the elevations shown on the Contract plans. All work done shall conform to all Federal, State, County and Local Regulations and permit conditions.

MATERIALS

Materials as indicated on the Contract plans.

CONSTRUCTION DETAILS

Drawings shall be submitted to the Engineer for review a minimum of two weeks prior to construction. The drawings shall show plan and cross-section of the proposed removal. The Engineer may waive the time requirement and/or the drawings if the Engineer deems the changes to be minor.

Temporary causeways shall be removed as indicated on the plans and in accordance with any regulatory agency permit conditions. Prior to removal, all temporary soil erosion and sediment control measures shall be installed in accordance with §209 of the Specifications.

Removal of the temporary causeways shall be performed in such a manner as to minimize turbidity and discharge of fine materials into the waterway. Additional temporary erosion control measures, as determined by the Engineer, may need to be employed to facilitate removal.

After removal of the temporary causeway, the channel bottom in areas of the existing temporary causeway, areas of causeway modification or areas of the channel bottom disturbed by the Contractor's operations shall be restored to original elevations as indicated on the contract plans. Temporary erosion control measures shall be maintained by the Contractor until the restored areas are stabilized.

METHOD OF MEASUREMENT

This work will be measured on a lump sum basis.

BASIS OF PAYMENT

The lump sum price bid shall include the cost of furnishing all labor, material, and equipment necessary to satisfactorily remove and dispose the existing temporary causeway, including land restoration measures and any additional temporary erosion control measures required to facilitate removal of the temporary causeways.

No partial payments will be made. One hundred (100) percent of the payment will be made when the existing temporary causeway is completely removed and disposed of and the temporary erosion control measures are removed and disturbed areas are stabilized.

ITEM 553.0404 09 - REMOVAL OF EXISTING TEMPORARY CAUSEWAYS

Payment will be made under:

<u>Item No.</u>	<u>Item Pay</u>	<u>Unit</u>
553.0404 09	Removal of Existing Temporary Causeways	Lump Sum