

ITEM 555.9911 10 M - PRECAST CONCRETE FASCIA UNITS

DESCRIPTION

This work shall consist of fabricating, furnishing and installing precast concrete fascia units in accordance with the contract documents and as directed by the Engineer.

MATERIALS

Materials for this work shall conform to the following:

Precast Units	Requirements of the Prestressed Concrete Construction Manual shall apply.
Bolts	ASTM A193M, Grade B6
Nuts and Washers	ASTM A194M, Grade 6 and ASTM A167
Grout	701-05

CONSTRUCTION DETAILS

The Contractor shall install the panels such that the intrados line is smooth and unbroken. All exposed faces shall be flush with each other.

The Contractor may install the panels before the prestressed beam is erected.

Bolts, nuts and washers shall be installed to the value given on the plans.

METHOD OF MEASUREMENT

This work will be measured as each precast concrete fascia units satisfactorily fabricated, furnished and installed.

BASIS OF PAYMENT

The unit price shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work.