

## **ITEM 08560.0401 M - STONE VENEER**

### **DESCRIPTION:**

This work shall consist of furnishing and placing stone masonry, with stone cap, of the type, size, shape, texture and color to match the existing stone masonry or as directed by the Engineer.

### **MATERIALS:**

The provisions of Section 560-2, Materials, shall apply with the following additions and modifications:

1. Dovetail anchors shall be as specified in 560-2.02 and spaced as indicated on drawings.

### **CONSTRUCTION DETAILS:**

The provisions of Section 560-3, Construction Details, shall apply with the following additions and modifications.

1. Stone veneer shall be laid in full bed of mortar with joints finished to match existing adjacent mortar in joint size, color and texture. Lay up stone veneer walls to match existing coursing of adjacent stone masonry.

The Contractor shall erect a sample panel of 2.3 square meters of each veneer style for approval by the Engineer. Prior to beginning work on the sample panel, the Contractor shall submit samples of stone to be used for approval by the Engineer. The sample panel shall be constructed on the new parapet. If the sample panel is approved, it shall remain on the wall and become part of the finished wall. If disapproved, it shall be removed and a new panel of 2.3 square meters constructed. There will not be any limitation on the number of sample panels required before approval is given.

### **METHOD OF MEASUREMENT:**

This work will be measured as the number of square meters of stone masonry furnished and installed except that the front vertical face of the stone cap shall be included in the area calculation. The remaining faces of the stone cap shall not be measured for payment.

### **BASIS OF PAYMENT:**

The unit price bid shall include the cost of all labor, materials, and equipment necessary to complete the work.