

## **ITEM 10560.1004 M - REMOVAL OF STONE MASONRY**

**DESCRIPTION.** The work shall consist of :

1. The removal and disposal of stone masonry.
2. The removal and storage of stone masonry.
3. The removal, match marking, and storage of stone masonry.

The exact nature of the work will be one, or a combination of, the foregoing operations as noted on the Contract Plans.

All work will be done at the locations indicated on the Contract Plans, or where ordered by the Engineer.

**MATERIALS.** Equipment proposed for this work shall be approved by the Engineer prior to actual use.

**CONSTRUCTION DETAILS.** All removal work shall be done in a manner satisfactory to the Engineer. Removal work will be limited to the limits indicated on the plans, or established in writing, by the Engineer.

If the removed stone masonry is to be disposed of, it shall become the property of the Contractor upon removal. Stone masonry shall be disposed of in a manner, and at a site, acceptable to the Engineer.

If the stone masonry is to be removed, and stored, or removed, matchmarked and stored, the Engineer will designate the place of storage. The manner of storage shall be acceptable to the Engineer. Matchmarkings shall be made with a weather resistant marker. Markings shall be placed such that they will not be visible when the masonry is reinstalled.

Damage to material not designated to be removed, caused by the Contractor's operations, shall be repaired by the Contractor in a manner satisfactory to the Engineer.

Stone masonry to be stored, which is damaged by the Contractor's operations, shall be repaired or replaced by the Contractor to the satisfaction of the Engineer.

**METHOD OF MEASUREMENT:** The quantity to be measured for payment will be the sum of the actual number of square meters of stone masonry removed and disposed of; removed and stored; and removed, match marked and stored. The measurement shall include the joints within the stone masonry.

## **ITEM 10560.1004 M - REMOVAL OF STONE MASONRY**

The measurement will be taken before the stone masonry is removed. The Contractor shall not remove any stone masonry until the measurement is completed and the Engineer authorizes the removal of the stone.

Except for coping stone removal, measurement will be taken on the plane of all the exposed surfaces of the stone masonry to be removed.

In the case of coping stone removal, measurement will be taken as the horizontal projection of the exposed surface of the coping stone.

Stone masonry indicated on the plans as not exposed to view will be considered as exposed for measurement purposes.

**BASIS OF PAYMENT:** The unit price bid per square meter shall include the cost of all labor, materials and equipment necessary to complete the work, including the providing of a disposal site and transportation to the site.

No payment will be made for repair work to material not designated for removal, damaged from the Contractor's operations.

No payment will be made for repairing or replacing stone masonry to be stored which is damaged by the Contractor's operations.