

ITEM 01560.1019 M - LABEL REMOVAL AND STORE STONE MASONRY

DESCRIPTION:

Label, diagram, and remove stone masonry from the locations indicated on the Contract Drawings such that the stones can be replaced in their original position. Clean and store all sound stone. Dispose of unsuitable stone and replace with new stone under another item.

MATERIALS:

None specified.

CONSTRUCTION DETAILS:

Make a photographic or other diagram of all stone in the walls to be removed and rebuilt, prior to disassembly. Submit a copy of the diagram to the Engineer. Label or mark all stone prior to, or during disassembly, to assure original placement in the rebuilt walls with the marks removed or hidden.

Clean the removed stone of all mortar, dirt and discoloration by means of steam or blast cleaning, hand tools or other methods, without damaging the stone. Remove stains by use of any stain remover which appears on the DOT's Approved List of Rust Stain Removers. Leave surface mortar if removal causes damage to the stones. Remove and dispose of all metal anchors, plates, and dowels from the stone masonry.

Neatly stockpile all cleaned and marked stone at a place and in a manner satisfactory to the Engineer, so that the Engineer can inspect and accurately determine the useable quantity. Promptly remove and dispose of all stone which the Engineer considers unsuitable for reuse.

Provide replacement stone in accordance with requirements of Subsection 560-2.03, Stone Masonry. Also, replace any stone damage by removal operations, at no cost to the State, if ordered by the Engineer.

METHOD OF MEASUREMENT:

The area will be measured, prior to initiation of work, as the number of square meters of stone wall face to be removed.

BASIS OF PAYMENT:

Include the cost of all labor and equipment necessary to complete the work in the unit price bid per square meter.