

## **ITEM 07560.1120 M - Construct Dry Stone Wall**

### **Description:**

Under this item, the Contractor shall construct a dry stone wall at the location and to the dimensions shown on the plants or as ordered by the Engineer.

### **Materials:**

Stone shall be native limestone, granite, or sandstone, sound and durable, and of uniform quality and texture throughout. Stone shall be free from shale, excess mica, seams, scaling or evidence of disintegration. Color shall be as specified. Samples of stone representative of the full range of sizes and colors shall be submitted to the Engineer for approval prior to commencement of work.

### **Construction:**

The Contractor shall construct the dry stone wall true to line and grade, and to the dimensions shown on the plans or as ordered by the Engineer.

A sample (approximate 4m) dry stone wall shall be constructed in order to assess pattern and workmanship to the satisfaction of the Engineer and Regional Landscape Architect. The Contractor may elect to construct the sample wall in place in anticipation of approval, in which case it may remain as a segment of the finished wall.

### **Method of Measurement:**

The quantity measured under this item will be the number of meters of dry stone wall constructed in accordance with the plans and the directions of the Engineer.

### **Basis of Payment:**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work. Excavation and backfill shall be paid for separately under the appropriate items.