

ITEM 08560.1308 M - REMOVE AND STORE STONE WALL

DESCRIPTION:

The contractor shall remove existing dry laid stone walls or portions thereof as shown on the plans or where directed by the Engineer, and store the stones for pick-up by others.

MATERIALS:

No materials are needed for this item.

CONSTRUCTION DETAILS:

All removal work shall be done in a manner satisfactory to the Engineer. Removal work will be confined to the limits indicated on the plans, or as established in writing, by the Engineer.

All stones removed shall remain the property of the property owner, and shall be stored at an on-site location designated by the Engineer. Damage to material not designated to be removed, caused by the contractor's operations, shall be repaired by the contractor at his own expense in a manner satisfactory to the Engineer.

METHOD OF MEASUREMENT:

The quantity to be measured for payment under this item shall be the number of meters measured along the top centerline of the wall to be removed.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, material and equipment necessary to complete the work.