

ITEM 07560.1320 M - REMOVE AND RESET STONE WALL

DESCRIPTION:

Under this item, the Contractor shall remove the existing stone wall from its original location and reset it at the location and to the dimensions as shown on the plans or as ordered by the Engineer.

MATERIALS:

The stone used shall be the existing material from the wall being removed.

At the Contractor's option, new clean stone matching the stone within the existing stone wall as to composition, nominal size, and appearance as approved by the Engineer may be utilized to construct the reset stone wall.

Masonry Mortar

Subsection 705-21

CONSTRUCTION DETAILS:

The Contractor shall carefully remove the existing stone wall as shown on the Plans or as ordered by the Engineer. All stone shall be cleaned and old mortar removed prior to reuse within the reset stone wall. The new wall shall be set true to line and to the dimensions shown on the Plans or as ordered by the Engineer. The workmanship shall duplicate that of the original installation.

METHOD OF MEASUREMENT:

The quantity to be measured under this item will be the number of meters of stone wall reset in accordance with the plans and the directions of the Engineer.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work. Excavation and backfill shall be paid for separately under the appropriate items.