

ITEM 08560.1320 M - REMOVE AND RESET STONE WALL

DESCRIPTION:

Under this item, the contractor shall remove the existing stone wall from its original location and reset it at the location and to the dimensions as shown on the plans or as directed by the Engineer.

MATERIALS:

The stone used shall be the existing material from the wall being removed. If this is insufficient or inadequate, the contractor shall supply an approved equal as determined by the Engineer at no additional cost to the State.

CONSTRUCTION DETAILS:

The contractor shall carefully remove the existing stone wall as shown on the plans or as directed by the Engineer. The new wall shall be set true to line and connected to the existing wall at the location(s) and to the dimensions as shown on the plans or as directed by the Engineer. The workmanship and construction manner shall duplicate those of the original installation.

Any damage caused by the contractor to the existing stone wall that is not incorporated into the new work shall be repaired by the contractor at his own expense to the satisfaction of the Engineer.

METHOD OF MEASUREMENT:

This work will be measured as the number of cubic meters of stone wall reset in accordance with the plans and the directions of the Engineer.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, materials and equipment necessary to complete the work.

Excavation and backfill shall be paid for separately under the appropriate items.