

Item 560.13200108 M – Removal and Repair of Existing Stone Wall

DESCRIPTION:

This work shall consist of removing and disposing of a portion of an existing stone wall and repairing of the remaining stone wall at locations indicated in the contract documents and as directed by the Engineer.

MATERIAL:

Mortar shall conform to the requirements of Subsection 560-2.06. Type S mortar will be used. All stone used to repair the existing stone wall shall be from the portion of wall that has been removed under this item. If this is insufficient or inadequate, the contractor shall supply an approved equal as determined by the Engineer.

CONSTRUCTION DETAILS:

The contractor shall carefully remove the portion of existing stone wall shown on the Plans or in the Proposal as ordered by the Engineer.

The remaining end sections shall be repaired to the dimensions shown. The workmanship and construction style shall duplicate that of the original installation. Reused stones are to be cleaned of old mortar and reset as approved by the Engineer. The footing of the wall section being removed shall remain, be cleaned of debris and shall be resurfaced to match adjacent surfaces.

Any damage to the remaining portion of the existing wall caused by the contractor's operations shall be repaired or replaced to the satisfaction of the Engineer at no expense to the State.

METHOD OF MEASUREMENT:

This work will be measured as the total number of cubic meters of stone wall measured prior to removal and repair, as indicated in the contract documents.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, material, and equipment necessary to complete the work.