

ITEM 07560.1321 M - REMOVE AND RESET STONE PILLARS

DESCRIPTION:

Under this item, the Contractor shall remove the existing stone pillars from their original location and place them at the locations shown on the plans or where directed by the Engineer.

MATERIALS:

Not specified.

CONSTRUCTION DETAILS:

The Contractor shall carefully remove the existing stone pillars and reset them as shown on the Plans or as ordered by the Engineer. Any damage caused by the Contractor to the stone pillars shall be repaired by the Contractor at his own expense to the satisfaction of the Engineer.

METHOD OF MEASUREMENT:

The quantity to be measured under this item will be the number of individual stone pillars reset in accordance with the plans and the directions of the Engineer.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work. Excavation and backfill shall be paid for separately under the appropriate items.