

ITEM 08560.1321 M - RELOCATE STONE WALL ENTRANCES

DESCRIPTION

This work shall consist of relocating existing stone wall entrances to the new location as shown on plans or as directed by Engineer.

MATERIALS:

The contractor shall furnish all additional new stone for the replacement of existing materials which are specified in the plans, damaged, or otherwise unsatisfactory in the opinion of the Engineer for the incorporation in the relocated stone wall entrances. All material furnished shall be approved by the Engineer and shall conform in type, size, kind, color, and shape to the existing.

Mortar	705-21
Concrete for Stemwall and Footing	501
Bar Reinforcement for Stemwall and Footing	709-01
Galvanized Steel anchor Slots (16mm)	719-01, Type IV
Stainless Steel Anchors	ASTM A167, Type 301, 302, or 304

CONSTRUCTION DETAILS

The contractor shall carefully dismantle and remove the existing stone wall entrances and salvage all materials specified in the plans and determined satisfactory by the Engineer for incorporation in the relocated entrances.

The contractor shall remove the existing stone masonry as shown on the plans or as directed by the Engineer. Prior to or during the removal of the stones, the contractor shall mark the existing stones and record the original location of the stones in a manner approved by the Engineer in order to insure that the stones are reset in their original location. All existing masonry to be reset shall be cleaned of old mortar to the satisfaction of the Engineer. If a stone is damaged and cannot be reset, the contractor shall supply the additional stone as needed. All masonry rejected by the Engineer shall become the property of the contractor for disposal.

The existing masonry shall be reset in accordance with requirements of Subsection 560-2.03 of the Standard Specifications - Stone Masonry, except that the sample wall shall not be required.

ITEM 08560.1321 M - RELOCATE STONE WALL ENTRANCES

METHOD OF MEASUREMENT:

This work will be measured as the number of meters of stone wall to be relocated.

BASIS OF PAYMENT

The unit price bid for this item shall include all labor, materials, and equipment necessary to complete the work.

Concrete footings and stems, footing excavation, and associated materials shall be included in the price bid for this item.