

ITEM 08560.1601 M - REMOVE, STORE AND RESET EXISTING STONE COPING
ITEM 08560.1602 M - REMOVE AND STORE EXISTING STONE COPING

DESCRIPTION:

This work shall consist of removing and storing existing stone coping at locations indicated on the plans and as directed by the Engineer.

The coping that is designated for reuse in this item shall be approved by the Engineer and reset as shown in the plans.

MATERIALS:

All stone coping is existing material.

Mortar used to reset the coping shall conform to the requirements of Subsection 560-2.06 of the Standard Specifications.

CONSTRUCTION DETAILS:

The contractor shall remove the existing stone coping from its original position, clean off the existing mortar, and store the coping at location(s) approved by the Engineer.

The coping that is to be reset shall be placed in accordance with the requirements of Subsection 560-3.02 of the Standard Specifications and as directed by the Engineer.

The stone coping that is to be stored but is not to be reset shall be picked up by others, designated by the Engineer, and removed from the project.

Coping that is to be reset and is damaged as a result of the contractor's operations shall be repaired or replaced by the contractor at no additional cost to the State.

METHOD OF MEASUREMENT:

This work will be measured as the number of meters of existing stone coping that is either removed, stored and reset or removed and stored, depending on the item specified. Measurement shall be taken along the centerline of the top surface of the coping.

BASIS OF PAYMENT:

The unit price bid shall include the cost of all labor, materials and equipment necessary to complete the work.

The cost of the fresh mortar bedding shall be included in this item for resetting the coping.