

ITEM 11560.1810 M - REMOVE AND RESET STONE MASONRY

DESCRIPTION

The work under this item shall include removing existing stone masonry, removing existing anchoring devices and furnishing and placing new anchoring devices, cleaning mortar, etc. from the stone, cataloguing and tagging each stone including a key drawing indicating location of each stone, storing and protecting the stones on pallets, and replacing the stone masonry including repair if required, as shown on the plans.

MATERIALS

The requirements of Subsections 560-2 and 560-2.06 shall apply.

CONSTRUCTION DETAILS

The requirements of Subsections 560-3.01 and 560-3.02, Sections A through E, shall apply.

METHOD OF MEASUREMENT

The method outlined in Subsection 560-4.04 shall apply with the exception that a sample wall will not be required nor measured.

BASIS OF PAYMENT

The basis of payment outlined in Subsection 560-5.03 shall apply. Progress payments will be made, at the unit bid, for 40% of the quantity when the masonry is removed, an additional 50% when the masonry is reset, and 10% when all remaining work is complete.