

ITEM 08560.2001 M - REMOVE AND RESTORE EXISTING CONCRETE BLOCK WALL

DESCRIPTION:

This work shall consist of removing a section of the existing concrete block wall (with parging and a concrete cap) and restoring the remaining wall as detailed in the contract documents and as directed by the Engineer.

MATERIALS:

The materials used for the repair of the restored concrete block wall shall conform to the requirements of Section 560 - Masonry and shall be approved by the Engineer prior to commencement of this work. If additional concrete blocks are needed to complete the wall restoration, they shall conform to the requirements of ASTM C90, Type I for normal weight concrete masonry units.

CONSTRUCTION DETAILS:

All wall removal work shall be performed in a manner satisfactory to the Engineer. The limits of the wall removal shall be indicated on the plans or as directed by the Engineer.

Damage to portions of the wall not designated to be removed, caused by the contractor's operations, shall be repaired by the contractor in a manner satisfactory to the Engineer at no expense to the State.

The restoration of the existing wall shall be as shown on the plans and as approved by the Engineer.

METHOD OF MEASUREMENT:

This work will be measured as a lump sum for the removal and restoration of the existing concrete wall.

BASIS OF PAYMENT:

The lump sum price bid shall include the cost of all labor, materials (including concrete repair material and additional concrete blocks), and equipment necessary to complete the work.