

**ITEM 11560.2006 M - REMOVE AND RESET MODULAR INTERLOCKING
CONCRETE BLOCK WALL**

DESCRIPTION

This work shall consist of removing and resetting modular interlocking concrete block planter wall in accordance with the contract documents and as directed by the Engineer.

MATERIALS

The modular interlocking concrete block used shall be the existing material from the planter wall being removed.

At the Contractor's option, new clean modular interlocking concrete block may be substituted subject to Engineer's approval. New block shall match the existing modular interlocking concrete in composition, nominal size, color and texture.

As part of the work excess modular interlocking concrete block that is in good condition shall be delivered to the Triborough Bridge and Tunnel Verrazano Narrows Bridge facility and be neatly stacked at the designated location.

Masonry Mortar

Subsection 705-21

CONSTRUCTION DETAILS

The new wall shall be set true to line and to the dimensions shown on the Plans or as ordered by the Engineer. The workmanship shall duplicate that of the original installation. A masonry mortar bed shall be provided to level the initial course of modular interlocking concrete block.

METHOD OF MEASUREMENT

This work will be measured as the number of square meters of remove and reset modular interlocking concrete block wall satisfactorily removed and reset.

BASIS OF PAYMENT

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work. Excavation and backfill shall be paid for separately under the appropriate items.