

ITEM 08560.21 M - REMOVE AND RESET EXISTING PARAPET

DESCRIPTION:

The contractor shall carefully remove the existing stone parapet, clean and reset the stone, where indicated on the plans or where directed by the Engineer.

MATERIALS:

The provisions of Section 560-2, Materials, shall apply with the following additions and modifications:

The existing stone shall be used as approved by the Engineer or the contractor shall supply additional stone to replace existing damaged stone, as needed, to complete the wall to the payment limits indicated on the plans. New stone shall be similar in all features to the existing stone and approved by the Engineer.

CONSTRUCTION DETAILS:

The contractor shall remove the existing stone parapet where indicated on the plans or where directed by the Engineer. The existing parapet, to be reset, shall be cleaned of old mortar to the satisfaction of the Engineer. All masonry rejected by the Engineer shall become the property of the contractor for disposal.

The existing mortar surface below the stone parapet designated to be removed shall be blown clean by compressed air to the satisfaction of the Engineer. All voids shall be filled with fresh mortar.

The existing parapet shall be reset in accordance with requirements of Subsection 560-3.04, Stone Masonry, except that the sample wall shall not be required.

METHOD OF MEASUREMENT:

This work will be measured as the number of square meters including joints within the stone parapet measured along the plane of the exposed surfaces (including the top, inside, outside and end faces) of the stone masonry, reset in its final location.

BASIS OF PAYMENT:

The unit price bid per square meter shall include the cost of all labor, materials and equipment necessary to satisfactorily complete the work as shown on the plans, including cleaning the masonry.