

ITEM 560.3201 11 – TEMPORARY SUPPORT BRACKET AT BRICK EROSION AREAS

DESCRIPTION.

This work shall consist of furnishing, installing and removing TEMPORARY SUPPORT BRACKET AT BRICK EROSION AREAS in accordance with the contract documents and as directed by the Engineer.

MATERIALS.

- A. Threaded Rod meeting ASTM A307 (SAE 1018) minimum.
- B. Anchoring Materials - Chemical Curing 701-07
- C. Structural Steel 715-01

CONSTRUCTION DETAILS.

Contractor shall furnish, install and remove TEMPORARY SUPPORT BRACKET AT BRICK EROSION AREAS.

Contractor shall perform the work strictly according to the construction sequence stated on the plans unless otherwise directed by the Engineer. Optionally, different construction methods may be submitted for review by the Department, but the Contractor shall be responsible for safe TEMPORARY SUPPORT BRACKET installation and removal under the alternate procedure.

For brick removal and replacement see contract items. For TEMPORARY SUPPORT BRACKET, see Specification Section 564- Structural Steel, and the contract documents.

METHOD OF MEASUREMENT.

This work will be measured as the number of meters of TEMPORARY SUPPORT BRACKET installed, accepted and removed at the brick erosion areas, in accordance with the contract documents or as directed by the Engineer.

BASIS OF PAYMENT.

The unit bid price per meter of bracket shall include the cost of furnishing all labor, materials and equipment necessary to complete the work.