

ITEM 11560.8001-REMOVE BRICK FACING

DESCRIPTION: Under this item, the Contractor shall remove existing brick facing from portions of existing walls where indicated on the plans or where directed by the Engineer.

MATERIALS: (Not Specified).

CONSTRUCTION DETAILS : The Contractor shall remove existing brick facing at the location shown on the plans or where directed by the Engineer, in a careful manner so as not to damage the existing structure or brick facing that is to remain. If required, this removal shall be performed in such a manner that the existing brick facing that is to remain will have a resultant saw-tooth type pattern to which new brick facing can be joined.

The removal of the existing brick facing shall include any mortar backing.

After removal of the existing brick facing, the Contractor is to clean the existing anchor slots in a manner approved by the Engineer.

All material removed under this item shall be properly disposed of the Contractor, off the Contract site.

Hand held chipping hammers or any other equipment approved by the Engineer may be used. After cleaning, the surface shall be air blown or vacuum cleaned.

METHOD OF MEASUREMENT:

Removal of brick facing will be measured by the actual number of square meter of existing brick facing removed as indicated on the plans or as directed by the Engineer.

BASIS OF PAYMENT:

The unit price bid per square meter shall include the cost of furnishing all labor, materials, and equipment necessary to remove and dispose of existing brick facing, off the site, including its mortar backing and the cleaning of existing anchor slots.