

ITEM 04563.05 M - PRECAST CONCRETE SLAB UNITS

CONSTRUCTION DETAILS:

The requirements of the New York State Prestressed Concrete Construction Manual shall apply. The Contractor shall have the option to deviate from the design shown in the Contract Plans in order to facilitate transportation and/or erection, or for other reasons. If the Contractor elects this option, he shall notify the Engineer immediately to discuss the proposed changes. If the Engineer agrees to the Contractor's proposed changes, the Contractor shall prepare design computations and plans, sealed by a Professional Engineer licensed in the State of New York, and submit them to the Engineer for approval.

METHOD OF MEASUREMENT:

The quantity to be paid for under this work shall be the number of square meters of plan area of each concrete slab unit installed. No deductions will be made for chamfers, shear keys, or notch cuts. Space between the units shall not be included in any measurement.

BASIS OF PAYMENT:

The unit price bid for these units shall include all labor, materials and equipment necessary to complete the work.

Damaged units which cannot be satisfactorily repaired or which do not meet dimensional tolerances shall be replaced by the Contractor at no cost to the State.