

**ITEM 563.0601 16 - PRESTRESSED CONCRETE DECK BULB TEES**

**DESCRIPTION**

This work shall consist of furnishing and installing Prestressed Concrete Deck Bulb Tees in accordance with the contract documents and as directed by the Engineer. The Contractor will notify the Engineer of the source of the prestressed units, for approval, within (7) days after the award of the contract.

**MATERIALS**

The concrete shall meet the requirements of §718-06, High Performance Concrete for Precast and Prestressed Bridge Beams. All other materials shall meet the requirements of Section 4 of the PCCM.

**CONSTRUCTION DETAILS**

The requirements of the PCCM shall apply.

**METHOD OF MEASUREMENT**

This work will be measured as the number of meters of Prestressed Concrete Deck Bulb Tees satisfactorily furnished and installed.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work, except that bearings will be paid for under their respective items.

Damaged units which cannot be satisfactorily repaired or which do not meet dimensional and camber tolerances shall be replaced by the Contractor at no cost to the State.

Progress payments will be made when each unit is furnished and placed in accordance with the plans and specifications exclusive of preparing and filling joints. Payment will be made at the unit price bid for 90% of the quantity properly placed. The balance of the quantity will be paid for upon completion of the work. The completion of work will include the correct preparation and filling of the joints.