

**ITEM 10567.50 M - INSTALLATION OF ARMORED JOINT SYSTEM WITH PREFORMED ELASTIC STRIP SEAL**

All provisions of item 567.50 M “Armored Joint System with Preformed Elastic Strip Seal” of the Standard Specifications shall apply except that the following materials required for the work will be furnished by the State:

1. Joint Angles
2. Joint Rails
3. Anchor Bolts
4. AZR Rubber Seal
5. Styrofoam B-Rod
6. Washers/Nuts

The Contractor shall notify the Engineer-In-Charge one week prior to pick up of the material and shall include the cost of picking up the above material, from the NYSDOT Region 10 storage yard located at the south side of Sunrise Highway East of William Floyd Parkway, in the above item.