

ITEM 568.7002--02 - RESETTING TRANSITION BRIDGE RAILING

DESCRIPTION

This work shall consist of removing, storing and resetting transition bridge railing including railings, posts and component parts in accordance with this specification and with the lines and grades shown on the plans or established by the Engineer.

MATERIALS

The provisions of Subsection 568-2 and 606-2.08 shall apply. Replacement materials, where required, shall meet the requirements of Subsections 568-2 and 606-2.08.

CONSTRUCTION DETAILS

The provisions of Subsections 568-3.01 shall apply.

METHOD OF MEASUREMENT

This work will be measured by the number of meters of transition bridge railing removed, stored and reset in accordance with field measurement and/or as directed by the Engineer.

BASIS OF PAYMENT

The unit price bid for each reset guide rail transition shall include the cost of furnishing all labor, equipment and material necessary to complete work. Any materials damaged due to the Contractor's operations shall be replaced at no additional cost to the state. Damaged guide rail posts determined to be unfit for reuse by the Engineer, shall be replaced with new materials and paid under the appropriate item.

Progress payments for removing, storing and resetting guide rail transitions will be made as follows:

1. 25% of the unit price bid for the quantity of transition bridge railing is removed and stored in accordance with the provisions of this specification.
2. 65% of the unit price bid for the quantity of transition bridge railing is reset in accordance with the provisions of this specification.
3. The balance of the unit price bid for the quantity of transition bridge railing is reset will be paid upon repair to the bituminous, concrete or other surfaces damaged by the resetting operations.