

ITEM 576.13 10 - CLEANING SCUPPERS

DESCRIPTION

The work shall consist of cleaning the 152 mm x 152 mm scuppers at the locations as shown on the Plans and directed by the Engineer. The work also includes disposing of the debris that has been cleaned out of the scuppers.

MATERIALS

None specified.

CONSTRUCTION DETAILS

The scuppers shall be cleaned after the timber planks has been removed at locations shown on the Plans and as directed by the Engineer.

The Contractor shall take proper precautions to prevent the debris from falling to the ground during the cleaning operations. All damages resulting from the Contractors operations shall be the responsibility of the Contractor.

All debris shall be disposed in a manner satisfactory to the Engineer.

METHOD OF MEASUREMENT

The work will be measured as the number of clogged scuppers satisfactorily cleaned out.

BASIS OF PAYMENT

The unit price bid includes the cost of furnishing all labor, materials and equipment necessary to complete the work described in this Specification, Plans and by the Engineer.