

ITEM 02576.27 M - REMOVE AND DISPOSE OF BRIDGE DRAINAGE TROUGHS

DESCRIPTION:

The work shall consist of removing and disposing of the existing drainage troughs where indicated in the contract documents and as directed by the Engineer. All material removed as part of this work shall become the property of the contractor and shall be removed from the work site.

MATERIALS:

Not specified.

CONSTRUCTION DETAILS:

The existing troughs shall be disconnected and removed from the structure for their entire length. All troughs and attendant supporting angles, plates, bolts and miscellaneous hardware shall be removed and disposed of.

METHOD OF MEASUREMENT:

The work shall be measured as the actual length measured to the nearest tenth of a meter of drainage troughs removed and disposed of. Measurement will be taken along the centerline of the trough.

BASIS OF PAYMENT:

The unit price bid shall include the cost of all labor, material and equipment necessary to complete the work, including the removal of all connections.