

ITEM 576.3000NN16 - TEMPORARY DRAINAGE SYSTEMS FOR STRUCTURES

DESCRIPTION:

Under this item the Contractor shall furnish, install, maintain, and remove a temporary drainage system as shown on the plans.

MATERIALS:

The following shall meet the requirements of Section 576-2 of the Standard Specifications:

A. Grating.

B. Bolts.

C. Drain Pipe.

D. Steel.

E. PVC Downspout.

Rubber Block Shall meet the requirements of Section 728-03, Plain Rubber Pad of the Standard Specifications (no testing will be required).

Asphalt Shall meet the requirements of Section 633-2 of the Standard Specifications.

CONSTRUCTION DETAILS:

The requirements of Section 576-3 of the Standard Specifications shall apply to the installation of the drainage system. The spaces between the grating and deck shall be filled in accordance with §633-3.

METHOD OF MEASUREMENT:

Payment will be made on a lump sum basis.

BASIS OF PAYMENT:

The lump sum price bid shall include all equipment, materials and labor necessary to furnish, install, maintain and remove the temporary drainage system for structures.

75% of the lump sum price shall be paid when the system has been installed and is operational; the balance shall be paid upon the removal of the system.

Note: NN denotes a serialized pay item.