

ITEM 05596.11 M - REMOVE, STORE AND REINSTALL OPEN STEEL FLOOR

DESCRIPTION

The work shall consist of removing, storing and reinstalling open steel floor at the locations indicated on the contract plans.

MATERIALS

Not applicable.

CONSTRUCTION DETAILS

The provisions of Subsections 596-3.01 Placement, 596-3.02 Field Welding, and 589-3 Removal of Existing Steel shall apply.

METHOD OF MEASUREMENT

The work will be measured as the number of square meters stated in the Estimate of Quantities shown on the plans. No field measurements shall be taken.

BASIS OF PAYMENT

- A. The unit price bid per square meter shall include the costs of all labor, material and equipment necessary to complete the work.
- B. Progress payments will be made in the following way:
 - 40% when the open steel floor is completely removed and stored.
 - 60% when the open steel floor is completely reinstalled.