

ITEM 599.2020 10 M - REMOVAL OF EXISTING WARNING GATES AND BIKEWAY GATES

DESCRIPTION

Under this item, the Contractor shall disconnect, remove all the warning gates and bikeway gates. The work shall include all labor, materials, equipment necessary to remove all warning gates and bikeway gates as indicated in the plans or as ordered by the engineer.

MATERIALS

None Specified.

CONSTRUCTION DETAILS

Removal

The removal of the warning and bikeway gates shall be done according to the stages of construction:

Stage 1: The contractor shall disconnect and carefully remove the existing southeast warning gate and bikeway gate assemblies, including roadway arms and mounting hardware, etc., from their existing locations as shown on the Contract Drawings.

Stage 3: After satisfactory completion of stage 1 construction, the Contractor shall disconnect, and carefully remove the existing northwest warning and bikeway gate assemblies, including roadway arms and mounting hardware, etc., from their existing locations as shown on the Contract Drawings.

METHOD OF MEASUREMENT

This work will be measured on a lump sum basis for all warning gate and bikeway gate removals.

BASIS OF PAYMENT

The price bid will include the cost of all labor, materials and equipment necessary to complete the work.