

Reason for DisApproval:

Spec is proprietary.

Contact Materials Bureau for new spec.

Spec DisApproved.

ITEM 601.9402 08 M - STREETPRINT DURATHERM TEXTURED ASPHALT PAVING

DESCRIPTION:

This work shall consist of furnishing and installing Streetprint DuraTherm Inlaid Thermoplastic Pavement System on hot mix asphalt (HMA).

MATERIALS:

The latest version of Streetprint DuraTherm Inlaid Thermoplastic Pavement System as issued by Integrated Paving Concepts Inc..

CONSTRUCTION DETAILS:

The contractor shall install the HMA. The HMA shall be placed according to Section 402. The surface temperature of the surface to be inlaid shall be 10 degrees Celsius or higher. At no time shall any of the reheating operations cause the pavement temperature to exceed 163 degrees Celsius. The equipment used for the inlaid operation shall be cleaned in accordance with subsection 402-3.12 Paver and Equipment Cleaning.

The applicator performing this work shall be an authorized StreetPrint DuraTherm applicator as licensed by Integrated Paving Concepts Inc.. The applicator shall submit verification of authorization to the Engineer 21 days before work commences. The applicator shall coordinate the installation with the contractor. The pattern and color shall be as indicated on the plans and shall be approved by the Regional Landscape Architect. The applicator shall follow the procedures detailed in the latest version of StreetPrint Application Procedures as issued by Integrated Paving Concepts Inc..

METHOD OF MEASUREMENT:

The installation of the StreetPrint DuraTherm System will be measured by the number of square meters of HMA satisfactorily inlaid in accordance with this specification and as approved by the Engineer.

BASIS OF PAYMENT:

The unit price bid per square meter shall include the cost of furnishing all labor, materials, equipment and tools necessary to complete the inlaid work. The HMA will be paid separately.